

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	URBAN
				80% FED. / 20% STATE	000.5
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1907		1907
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	573		573
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	635		635
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	358		358
55100500	STORM SEWER REMOVAL 12"	FOOT	50		50
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	58		58
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		3
60250200	CATCH BASINS TO BE ADJUSTED	EACH	19		19
60255500	MANHOLES TO BE ADJUSTED	EACH	11		11
60260100	INLETS TO BE ADJUSTED	EACH	1		1
60500050	REMOVING CATCH BASINS	EACH	5		5
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50		50
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1400		1400
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1

\* Specialty Items

FILE NAME = 0160409-SHT-500.dgn	USER NAME = Anthony.Pluta	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SHT_PLAN	PLOT SCALE = 1/8"=1'-0"	DRAWN -	REVISED -					330	2012-0881	COOK	152	5
DTG:\W09-SHT-500.dgn 1/18/2013 1:05:00 PM	PLOT DATE = 1/18/2013	CHECKED -	REVISED -		SCALE:	SHEET 2 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 60W09			
	DATE = 01/02/13	DATE	REVISED -						ILLINOIS FED. AID PROJECT			