


SUMMARY OF QUANTITIES (CONTD.)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,434	4,434				
40600300	AGGREGATE (PRIME COAT)	TON	133	133				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	117	117				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,965	2,965				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,395	2,395				
40701946	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/4"	SQ YD	11,691	11,691				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	49	49				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	48	48				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10,277	10,277				
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	80	80				
42400800	DETECTABLE WARNINGS	SQ FT	269	269				
44000100	PAVEMENT REMOVAL	SQ YD	11,329	11,329				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,758	1,758				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,072	4,072				
44000600	SIDEWALK REMOVAL	SQ FT	235	235				
44004000	PAVED DITCH REMOVAL	FOOT	979	979				
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	110	110				
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	665	665				
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	110	110				
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	110	110				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,206	6,206				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,831	1,831				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4,272	4,272				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1				
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1				
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4				
50105220	PIPE CULVERT REMOVAL	FOOT	765	765				
50200100	STRUCTURE EXCAVATION	CU YD	740		740			
50300225	CONCRETE STRUCTURES	CU YD	220		220			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	38,440		38,440			

* SPECIALTY ITEM

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: 12/20/2012 9:40:01 AM
 DATE PLOTTED: 08/06/22 - sum.dgn
 FILE NAME: 08/06/22 - sum.dgn
 PLOT DRIVER: pdf_bw_no_invel.plt
 PEN TABLE: standard.ctb



USER NAME = jattano	DESIGNED - JRM	REVISED - 3/1/13
FILE NAME = 080622-sum.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 12/20/2012	DATE - 12/20/12	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 2 OF 8 SHEETS	STA.	TO STA.

F.A.U. RTE. 168	SECTION 05-00314-00-WR	COUNTY MCHENRY	TOTAL SHEETS 187	SHEET NO. 5
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 63515		