

PJOHN	PRE-STAGE (CU YD)				STAGE 1 (CU YD)				STAGE 2 (CU YD)				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) WITH 20% SHRINKAGE	
	STATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EMBANKMENT	AGGREGATE SUBGRADE IMPROVEMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EMBANKMENT	AGGREGATE SUBGRADE IMPROVEMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EMBANKMENT	AGGREGATE SUBGRADE IMPROVEMENT	STAGE 1
129+16.78	0.0	0.0	0.0	0.0	19.8	43.0	1.5	15.4	12.9	28.3	0.6	12.4	32.9	22.0
129+50.00	0.0	0.0	0.0	0.0	43.5	89.3	9.4	32.1	25.2	52.7	4.6	23.9	62.1	37.6
130+00.00	0.0	0.0	0.0	0.0	69.3	131.0	22.7	52.5	38.0	70.4	7.8	35.2	82.1	48.5
130+50.00	0.0	0.0	0.0	0.0	50.6	86.9	45.9	34.0	23.4	37.5	23.2	20.0	23.6	6.8
130+83.05	0.0	0.0	0.0	0.0	19.4	28.2	38.4	8.4	5.3	7.2	26.4	3.2	-15.9	-20.7
131+00.00	0.0	0.0	0.0	0.0	10.0	12.8	14.8	4.2	3.1	3.9	13.0	1.6	-4.6	-9.9
131+50.00	0.0	0.0	0.0	0.0	14.9	19.4	24.8	6.3	15.6	13.6	51.8	4.9	-9.3	-40.9
132+00.00	0.0	0.0	0.0	0.0	0.0	0.0	1.9	0.0	10.7	7.9	33.0	2.5	-1.9	-26.7
132+50.00	0.0	0.0	0.0	0.0	4.2	3.9	21.7	0.9	2.8	6.3	23.1	2.4	-18.6	-18.1
133+00.00	0.0	0.0	0.0	0.0	9.9	3.9	45.0	0.9	9.4	9.8	51.9	2.8	-41.9	-44.0
134+00.00	0.0	0.0	0.0	0.0	14.8	0.0	89.1	0.0	31.3	7.0	146.7	0.7	-89.1	-141.0
134+50.00	0.0	0.0	0.0	0.0	4.8	0.0	43.1	0.0	11.9	0.0	75.4	0.0	-43.1	-75.4
135+00.00	0.0	0.0	0.0	0.0	4.1	0.0	47.2	0.0	4.4	0.0	61.2	0.0	-47.2	-61.2
135+50.00	0.0	0.0	0.0	0.0	7.3	0.0	45.7	0.0	4.5	3.1	56.8	0.0	-45.7	-54.3
136+00.00	0.0	0.0	0.0	0.0	6.4	0.0	45.4	0.0	6.1	5.7	55.8	0.0	-45.4	-51.2
136+50.00	0.0	0.0	0.0	0.0	0.4	0.0	47.4	0.0	7.2	6.1	57.3	0.0	-47.4	-52.4
137+00.00	0.0	0.0	0.0	0.0	3.6	0.0	44.6	0.0	8.4	4.7	60.2	0.0	-44.6	-56.4
137+50.00	0.0	0.0	0.0	0.0	7.6	0.0	46.1	0.0	9.2	3.0	61.4	0.0	-46.1	-59.0
138+00.00	0.0	0.0	0.0	0.0	9.7	0.0	50.0	0.0	10.4	4.0	55.6	0.0	-50.0	-52.4
138+50.00	0.0	0.0	0.0	0.0	11.2	0.0	50.3	0.0	13.1	9.7	46.0	0.7	-50.3	-38.2
139+00.00	0.0	0.0	0.0	0.0	12.4	0.0	46.7	0.0	15.6	14.9	36.0	2.6	-46.7	-24.1
139+50.00	0.0	0.0	0.0	0.0	16.6	11.6	35.9	1.7	19.4	28.1	30.3	6.0	-26.7	-7.8
140+00.00	0.0	0.0	0.0	0.0	26.4	73.1	25.3	4.1	24.6	45.1	25.9	8.9	33.2	10.1
140+50.00	0.0	0.0	0.0	0.0	38.4	181.4	22.8	5.2	28.8	50.5	24.6	9.2	122.3	15.7
141+00.00	0.0	0.0	0.0	0.0	44.6	264.8	20.7	6.0	28.0	40.6	25.1	8.8	191.1	7.4
141+50.00	0.0	0.0	0.0	0.0	41.9	234.3	19.7	6.8	24.0	27.3	27.6	8.1	167.7	-5.7
142+00.00	0.0	0.0	0.0	0.0	34.6	132.9	20.2	7.0	23.0	31.1	30.6	7.3	86.1	-5.7
142+50.00	0.0	0.0	0.0	0.0	29.4	80.9	22.7	7.1	20.9	35.4	30.3	6.6	42.1	-2.0
143+00.00	0.0	0.0	0.0	0.0	27.7	64.1	23.8	8.1	17.7	23.1	32.3	4.9	27.5	-13.9
143+50.00	0.0	0.0	0.0	0.0	24.7	42.3	23.5	8.6	17.3	11.1	70.3	3.7	10.3	-61.4
143+76.59	0.0	0.0	0.0	0.0	13.8	20.4	11.4	4.5	9.8	5.5	55.9	2.0	4.9	-51.5
144+00.00	0.0	0.0	0.0	0.0	11.8	16.3	10.9	4.0	7.2	5.8	37.8	1.7	2.1	-33.1
144+50.00	0.0	0.0	0.0	0.0	20.1	21.9	29.6	7.9	10.8	11.7	48.9	1.9	-12.1	-39.6
144+68.84	0.0	0.0	0.0	0.0	7.6	8.4	11.8	2.7	3.5	3.6	15.2	0.0	-5.1	-12.3
145+00.00	0.0	0.0	0.0	0.0	14.4	18.1	20.2	4.7	5.7	8.2	32.0	1.4	-5.7	-25.4
145+50.00	0.0	0.0	0.0	0.0	26.2	39.4	34.6	7.7	12.3	15.5	62.5	4.1	-3.1	-50.1
146+00.00	0.0	0.0	0.0	0.0	34.5	52.5	39.9	7.0	13.5	16.0	56.0	3.7	2.1	-43.2
146+50.00	0.0	0.0	0.0	0.0	30.5	37.9	41.9	6.9	10.8	13.7	53.6	3.7	-11.6	-42.6
147+00.00	0.0	0.0	0.0	0.0	15.9	13.8	38.4	7.2	11.7	9.4	58.5	3.8	-27.4	-51.0
147+50.00	0.0	0.0	0.0	0.0	11.0	9.7	46.3	3.6	15.5	10.3	59.4	4.0	-38.5	-51.1
148+00.00	0.0	0.0	0.0	0.0	10.3	11.4	52.1	1.9	16.1	15.5	46.4	5.1	-43.0	-34.0
148+50.00	0.0	0.0	0.0	0.0	16.0	18.4	39.1	5.3	16.0	19.4	29.5	6.4	-24.3	-14.0
149+00.00	0.0	0.0	0.0	0.0	21.9	23.8	29.8	6.8	16.0	17.3	26.5	6.8	-10.8	-12.6
149+50.00	0.0	0.0	0.0	0.0	25.2	30.6	32.4	7.1	20.0	18.1	27.8	6.1	-8.0	-13.3
150+00.00	0.0	0.0	0.0	0.0	27.1	31.2	40.7	7.2	28.0	34.9	31.1	5.9	-15.8	-3.2
150+50.00	0.0	0.0	0.0	0.0	28.9	28.5	49.7	7.4	28.3	44.6	38.4	6.4	-26.9	-2.7
151+00.00	0.0	0.0	0.0	0.0	34.1	25.8	49.6	7.4	26.9	47.1	37.7	6.2	-29.0	0.0
151+50.00	0.0	0.0	0.0	0.0	31.8	18.1	49.4	7.0	28.1	58.0	33.4	6.0	-34.9	12.9
152+00.00	0.0	0.0	0.0	0.0	25.0	14.1	48.1	6.0	29.6	80.2	28.8	6.2	-36.9	35.4
152+50.00	0.0	0.0	0.0	0.0	24.9	15.8	42.2	5.7	31.1	91.1	25.7	6.5	-29.6	47.1
153+00.00	0.0	0.0	0.0	0.0	26.6	28.1	40.0	6.4	32.7	89.8	29.9	6.8	-17.6	41.9
153+50.00	0.0	0.0	0.0	0.0	26.9	39.9	38.7	6.5	34.5	98.5	35.7	6.9	-6.8	43.1
154+00.00	0.0	0.0	0.0	0.0	27.9	46.3	39.8	6.4	35.4	107.2	39.1	7.0	-2.8	46.7
154+50.00	0.0	0.0	0.0	0.0	29.5	44.6	36.5	6.7	35.1	73.2	32.1	7.3	-0.8	26.5
154+62.20	0.0	0.0	0.0	0.0	7.2	9.4	7.5	1.7	6.2	8.6	5.8	1.8	0.0	1.1
155+00.00	0.0	0.0	0.0	0.0	21.1	26.7	24.4	5.2	14.9	20.6	25.7	5.4	-3.0	-9.2
155+50.00	0.0	0.0	0.0	0.0	28.0	43.1	31.5	6.9	24.4	17.4	46.8	7.0	3.0	-32.8
156+00.00	0.0	0.0	0.0	0.0	46.2	61.2	33.9	12.3	25.3	16.6	51.7	6.9	15.1	-38.4
156+50.00	0.0	0.0	0.0	0.0	48.6	56.0	81.9	14.3	25.9	15.2	58.8	6.9	-37.0	-46.6
157+00.00	0.0	0.0	0.0	0.0	34.1	43.7	101.2	10.9	25.7	15.9	57.9	6.9	-66.2	-45.1
157+50.00	0.0	0.0	0.0	0.0	37.5	49.2	95.5	10.9	29.4	20.4	50.3	6.9	-56.1	-34.0
158+00.00	0.0	0.0	0.0	0.0	28.1	52.2	74.5	10.9	25.5	18.7	45.6	6.9	-32.8	-30.6

COMPANY NAME: HRGreen
PROJECT CONTACT: HRGreen.com
DATE PLOTTED: 12/19/2012 2:24:36 PM
PLOT SCALE: N.T.S.
PLOT DRAFTER: JPA
PER TABLE: TH



USER NAME = jottano	DESIGNED - JRM	REVISED -
FILE NAME = 000622-sch-01.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 12/19/2012	DATE - 12/19/12	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
JOHNSBURG ROAD RECONSTRUCTION**

SCALE: N.T.S. SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00314-00-WR	MCHENRY	187	13
CONTRACT NO.			63515	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				