

SUMMARY OF QUANTITIES

SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					CMAQ		
					100% VILLAGE	80% FED 20% VILLAGE	
					STREETSCAPE 0031	ROADWAY 0021	
					URBAN	URBAN	
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	235		235	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	58		58	
	20101000	TEMPORARY FENCE	FOOT	175		175	
Δ	20101200	TREE ROOT PRUNING	EACH	8		8	
Δ	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	53		53	
Δ	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	53		53	
Δ	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	53		53	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1363		1363	
Δ	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5024		5024	
Δ	25200110	SODDING, SALT TOLERANT	SQ YD	5024		5024	
Δ	25200200	SUPPLEMENTAL WATERING	UNIT	38		38	
	28000510	INLET FILTERS	EACH	27		27	
	35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	683		683	
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	3		3	
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	21		21	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	24		24	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NS0	TON	2		2	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	769		769	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31254		31254	
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	5543		5543	
	42400800	DETECTABLE WARNINGS	SQ FT	834		834	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1410		1410	
	44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	851		851	
	44000600	SIDEWALK REMOVAL	SQ FT	17892		17892	
	60255500	MANHOLES TO BE ADJUSTED	EACH	5		5	
	60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-8.12	FOOT	793		793	

SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					CMAQ		
					100% VILLAGE	80% FED 20% VILLAGE	
					STREETSCAPE 0031	ROADWAY 0021	
					URBAN	URBAN	
	63200310	GUARDRAIL REMOVAL	FOOT	14		14	
	63700175	CONCRETE BARRIER, SINGLE FACE, 42-INCH HEIGHT	FOOT	290		290	
	67100100	MOBILIZATION	L SUM	1		1	
Δ	69900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2000		2000	
Δ	69900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1	
Δ	69900530	SOIL DISPOSAL ANALYSIS	EACH	5		5	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1	
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1		1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
Δ	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	22		22	
Δ	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	534		534	
Δ	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	16		16	
Δ	B2003116	TREE, MALUS CORALBURST, (CORALBURST CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	18		18	
Δ	C2C06918	SHRUB, SPIREA X BUMALDA GOLDFLAME (GOLD FLAME BUMALDA SPIREA), 18" HEIGHT CONTAINER	EACH	5		5	
Δ	C2C12924	SHRUB VIBURNUM TRILOBUM BAILEY COMPACT (BAILEY COMPACT AMERICAN CRANBERRY VIBURNUM), 2' HEIGHT, CONTAINER	EACH	10		10	
Δ	C2C15761	SHRUB, SPIREA JAPONICA NEON FLASH (NEON FLASH JAPANESE SPIREA), 18" HEIGHT, 5 GALLON CONTAINER	EACH	11		11	
Δ	K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	24		24	
Δ	K0028930	SHRUB REMOVAL	EACH	57		57	
Δ	X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	2		2	
Δ	XX000959	TRASH RECEPTACLES	EACH	4		4	
Δ	XX002133	RELOCATE SIGN AND BASE	EACH	2		2	
Δ	XX008429	SIDEWALK, SPECIAL	SQ FT	126		126	
Δ	XX008868	STAMPED COLORED PORTLAND CEMENT CONCRETE	SQ FT	480		480	
Δ	Z0003650	BENCHES	EACH	4		4	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1	
Δ	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	27		27	
	Z0062000	SAW CUTTING	FOOT	1598		1598	
	Z0076600	TRAINEES	HOOR	500		500	
	Z0076600	TRAINEES TPG	HOOR	500		500	

Δ SPECIALTY ITEMS

PLAN SURVEYED BY DATE  
 AS DRAWN BY DATE  
 CHECKED BY DATE  
 IN CHARGE BY DATE  
 NO. OF SHEETS 17 OF 17  
 NO. OF THIS SHEET 3 OF 3

PROJECT TITLE  
 DATE  
 NO. OF SHEETS 17 OF 17  
 NO. OF THIS SHEET 3 OF 3

DESIGNED - TMC	REVISOR - 7-26-2012
DRAWN - TMC	REVISOR
CHECKED - AUB	REVISOR
DATE - 8-16-2010	REVISOR

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCALE:	F.A.U. R.T.E. 1273	SECTION 02-00095-00-SW	COUNTY COOK	TOTAL SHEETS 17	SHEET NO. 3
CONTRACT NO. 63614			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		