

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	NON-PARTICIPATING
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION		
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6		5		1												
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1				1												
60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2				2												
60254340	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	3				3												
60255500	MANHOLES TO BE ADJUSTED	EACH	17	1	10		5	1											
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1				1												
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1															
60260100	INLETS TO BE ADJUSTED	EACH	2				2												
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1				1												
X 60265700	VALVE VAULTS TO BE ADJUSTED	EACH	19		5		2	1											11
X 60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	3		2														1
X 60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1																1
X 60266600	VALVE BOXES TO BE ADJUSTED	EACH	16		2		2												12
60500040	REMOVING MANHOLES	EACH	4		4														
60500050	REMOVING CATCH BASINS	EACH	14	1	9		4												
60500060	REMOVING INLETS	EACH	19	1	16		1	1											
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	5		1		4												
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	7		7														
60500105	FILLING MANHOLES	EACH	5		5														
60500205	FILLING CATCH BASINS	EACH	20		9		11												
60500305	FILLING INLETS	EACH	9		5		4												
60600605	CONCRETE CURB, TYPE B	FOOT	129		78		51												
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2792	730	364		911	787											
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	9733	77	6533		3113	10											
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	553				553												
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	362		362														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4411		2660		1751												
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	6890		5633		1257												
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	374		374														
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	84				84												
60624600	CORRUGATED MEDIAN	SQ FT	265		108		157												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	14		7		7												
67100100	MOBILIZATION	L SUM	1		0.5		0.5												
70106800	CHANGEABLE MESSAGE SIGN	CAL MD	68		33		33		2										
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10942	1302	5263		3167	1210											
70300210	TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS	SQ FT	6542	358	3744		2217	223											

X SPECIALTY ITEM

FILE NAME = J:\2329\cad\sheet\2329_530.dgn

USER NAME = djc
 PLOT SCALE = 50.0000 1/1 in.
 PLOT DATE = 12/7/2012

DESIGNED - JAT
 DRAWN - JAT
 CHECKED - DJK
 DATE - 8-20-12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 4 OF 10 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074-00-CH	COOK	245	7
CONTRACT NO. 63629				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-CM-6003051				