

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	0031
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	
X 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1523					147	37					1339				
X 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1905					882	442					581				
X 81400100	HANDHOLE	EACH	17					5	4	2				6				
X 81400200	HEAVY-DUTY HANDHOLE	EACH	8					4	4									
X 81400300	DOUBLE HANDHOLE	EACH	5					3	2									
X 81603085	UNIT DUCT, 600V, 3-1/C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	12451											12451				
X 81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	145											145				
X 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	9454											9454				
X 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	34											34				
X 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	26											26				
X 83050910	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 FT. MAST ARMS	EACH	4											4				
X 83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	2											2				
X 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	44											44				
X 83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	2											2				
X 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	69											69				
X 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	36											36				
X 84200804	REMOVAL OF POLE FOUNDATION	EACH	41			3	1							37				
X 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2											2				
X 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2											2				
X 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2											2				
X 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2											2				
X 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1							1								
X 86400100	TRANSCIEVER - FIBER OPTIC	EACH	2					1	1									
X 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3214								3214							
X 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3159					1792	1367									
X 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4770					3042	1728									
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4663					3456	1207									
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4532					2152	2380									
X 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7515					4958	2557									
X 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	264					202	62									
X 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2196					1402	794									
X 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2					2										
X 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4						4									
X 87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	2					2										
X 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1					1										
X 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1					1										

X SPECIALTY ITEM

FILE NAME = J:\2329\ood\sheet\2329\_S00.dgn  
 USER NAME = d.jk  
 PLOT SCALE = 50.0000 / 1.00  
 PLOT DATE = 5/17/2012

DESIGNED - JAT  
 DRAWN - JAT  
 CHECKED - DJK  
 DATE - 8-20-12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 6 OF 10 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074-00-CH	COOK	245	9
CONTRACT NO. 63629			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-CMM-8003051	