

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	0031
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	NON-PARTICIPATING
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	
X 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1					1										
X 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	3					1	2									
X 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1						1									
X 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1						1									
X 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	2					2										
X 87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1					1										
X 87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1					1										
X 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20					4	16									
X 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8					4	4									
X 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	90					60	30									
X 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	75					45	30									
X 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21					21										
X 87900200	DRILL EXISTING HANDHOLE	EACH	1							1								
X 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	16					12	4									
X 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	14					8	6									
X 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2						2									
X 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2						2									
X 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	12					4	8									
X 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2					2										
X 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	30					20	10									
X 88500100	INDUCTIVE LOOP DETECTOR	EACH	25					15	10									
X 88600100	DETECTOR LOOP, TYPE I	FOOT	1933					871	1062									
X 88700200	LIGHT DETECTOR	EACH	6															6
X 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2															2
X 88800100	PEDESTRIAN PUSH-BUTTON	EACH	16					8	8									
X 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1										
X 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	33011							560					32451			
X 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1										
X 89502380	REMOVE EXISTING HANDHOLE	EACH	13					11	2									
X 89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1					1										
X 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	16		5			9										2
X A2000220	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2															2
X A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5												3			2

X SPECIALTY ITEM