

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0005	0005	0005	0021	0021	0021	0021	0021	0021	0021	0031	0031	0031	NON-PARTICIPATING
				RECONSTRUCTION, NO CAPACITY ADDED	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SYSTEM PRESERVATION, RESURFACING	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (TRAFFIC SIGNALS)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	
				HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	HOLMES WAY	BARRINGTON ROAD / SCHAUMBURG ROAD	BARRINGTON ROAD / HOLMES WAY	INTERCONNECT	HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD		HOLMES WAY	BARRINGTON ROAD	SCHAUMBURG ROAD	
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	252		105	147												
X X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	586		252	218												116
X X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	28											28				
X X8250060	TEMPORARY LIGHTING CONTROLLER	EACH	1															1
X X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1															1
X X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	100															100
X X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8"	EACH	43															43
X X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2					1	1									
X X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	2					1	1									
X X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	3260								3260							
X X8950215	RELOCATE EXISTING HANDHOLE	EACH	4															4
X XX002136	PRESSURE CONNECTION	EACH	2		1	1												
X XX003848	GYPSON PLACEMENT	POUND	284															284
X XX004913	REMOVE FIBER OPTIC CABLE FROM CONDUIT	FOOT	571								571							
XX005636	PIPE UNDERDRAINS, PERFORATED POLYVINYLCHLORIDE PIPE, 6"	FOOT	475			475												
X XX006159	MEDIAN SOIL MIX FURNISH AND PLACE	CU YD	290															290
X XX006329	RPZ ENCLOSURE 2"	EACH	1															1
X XX006826	REMOVE AND RELOCATE LAWN SPRINKLER SYSTEM	FOOT	400		200.0	200.0												
X XX007184	RPZ BACKFLOW PREVENTER, 1 1/2", TYPE 1	EACH	1															1
Z0004526	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 7"	SQ YD	763	314	449													
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1	1												
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50		30	20												
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	6365		3720	2645												
X Z0020150	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2													
X Z0020258	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2													
X Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	394	54	139	176	25											
X Z0035028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	14											14				
X Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1							1								
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	483		281	136	66											
Z0062456	TEMPORARY PAVEMENT	SQ YD	1911		1019	892												
X Z0070200	SURVEY MONUMENTS	EACH	2			2												
X Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1					1										
O Z0076600	TRAINEES	HOUR	500		250	250												
O Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500		250	250												
X 81603072	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA, POLYETHYLENE	FOOT	232											232				
X XX008735	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, PAINTED	EACH	14											14				

X SPECIALTY ITEM