

SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION							
BARRINGTON ROAD - STAGE 1							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
203+03.28		10.1	3.5				
	46.72			9.8	3.5	17.0	6.1
203+50		9.5	3.5				
	50			11.1	4.2	20.5	7.7
204+00		12.6	4.9				
	50			11.7	4.3	21.6	7.9
204+50		10.8	3.7				
	50			11.5	3.7	21.4	6.9
205+00		12.3	3.8				
	50			12.1	3.9	22.3	7.2
205+50		11.8	4.1				
	50			12.4	5.5	23.0	10.2
206+00		13.0	7.0				
	50			6.5	3.5	12.0	6.4
206+50		0.0	0.0				
	50			7.4	2.0	13.7	3.8
207+00		14.8	4.1				
	50			14.1	3.7	26.2	6.8
207+50		13.5	3.3				
	50			13.4	3.3	24.9	6.1
208+00		13.4	3.3				
	50			13.3	3.4	24.7	6.2
208+50		13.2	3.4				
	50			12.6	3.8	23.3	7.0
209+00		11.9	4.2				
	50			11.3	4.1	20.9	7.7
209+50		10.6	4.0				
	50			22.8	3.1	42.3	6.7
210+00		35.0	2.1				
	50			46.8	3.0	86.7	5.5
210+50		58.7	3.9				
	50			47.2	3.6	87.5	6.6
211+00		35.8	3.3				
	50			35.9	3.3	66.5	6.2
211+50		36.0	3.3				
	50			37.2	3.5	68.8	6.4
212+00		38.3	3.6				
	50			38.8	3.7	71.6	6.8
212+50		39.3	3.7				
	50			39.5	3.8	73.1	7.0
213+00		39.7	3.9				
	50			39.4	3.8	72.9	7.1
213+50		39.0	3.8				
	50			40.5	3.5	75.1	6.5
214+00		42.0	3.3				
	50			42.0	3.2	77.8	6.0
214+50		42.0	3.2				
	50			61.8	3.2	114.5	6.0
215+00		61.6	3.2				
	50			40.8	1.6	75.6	3.0
215+50		0.0	0.0				
	50			8.0	0.0	14.7	0.0
216+00		15.9	0.0				
	50			26.8	1.8	49.6	3.4
216+50		37.6	3.7				
	50			25.7	3.8	47.6	7.1
217+00		13.8	4.0				
	50			13.5	4.0	25.1	7.4
217+50		13.3	4.0				
	50			13.8	4.0	25.5	7.4
218+00		14.3	3.9				
	50			15.7	3.8	29.0	6.9

(CONTINUED)							
BARRINGTON ROAD - STAGE 1							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
218+50		17.1	3.6				
	50			16.4	3.6	30.3	6.6
219+00		15.6	3.6				
	50			15.9	3.6	29.5	6.7
219+50		16.2	3.6				
	50			14.8	3.7	27.3	6.9
220+00		13.4	3.8				
	50			15.0	3.9	27.7	7.1
220+50		16.6	3.9				
	50			17.2	4.0	31.8	7.4
221+00		17.8	4.1				
	50			18.3	4.1	33.9	7.6
221+50		18.8	4.1				
	50			18.6	4.0	34.5	7.4
222+00		18.4	3.9				
	50			15.4	7.0	28.6	12.9
222+50		12.4	10.0				
	50			14.1	5.1	26.2	9.5
223+00		15.9	0.2				
	50			16.1	4.1	29.7	7.6
223+50		16.3	8.0				
	50			11.6	6.7	21.5	12.4
224+00		6.9	5.4				
	50			8.6	5.0	15.9	9.3
224+50		10.3	4.7				
	50			10.4	4.7	19.3	8.6
225+00		10.5	4.6				
	50			10.2	4.3	19.0	8.0
225+50		10.0	4.0				
	50			9.9	3.8	18.3	7.0
226+00		9.8	3.6				
	50			10.2	3.8	18.9	7.1
226+50		10.6	4.0				
	50			10.7	3.9	19.8	7.3
227+00		10.8	3.9				
	50			10.7	3.8	19.9	7.0
227+50		10.7	3.7				
	50			10.3	3.7	19.0	6.8
228+00		9.9	3.6				
	50			7.9	3.6	14.7	6.7
228+50		6.0	3.7				
	50			3.0	1.8	5.6	3.4
229+00		0.0	0.0				
	50			3.7	4.6	6.9	8.6
229+50		7.4	9.2				
	50			8.7	6.0	16.2	11.2
230+00		10.1	2.9				
	50			9.8	3.0	18.2	5.5
230+50		9.6	3.1				
	50			10.0	3.2	18.5	5.9
231+00		10.4	3.4				
	50			11.3	3.3	20.8	6.1
231+50		12.1	3.2				
	50			12.0	3.2	22.2	5.9
232+00		11.9	3.1				
	50			11.0	3.2	20.4	6.0
232+50		10.1	3.4				
	50			9.4	3.3	17.3	6.1
233+00		8.6	3.2				
	50			8.7	3.3	16.2	6.2
233+50		8.9	3.4				
	28.58			9.0	3.5	9.5	3.7
233+78.68		9.0	3.5				
BARRINGTON ROAD - STAGE 1 TOTAL						2,033.1	423.8

FILE NAME = ...load\sheet\2329\_Schedule\_02.dgn

USER NAME = v\_djk  
 PLOT SCALE = 1/8" = 1' / in  
 PLOT DATE = 8/16/2012

DESIGNED - JAT  
 DRAWN - JAT  
 CHECKED - DJK  
 DATE - 8-20-12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 2 OF 9 SHEETS

P.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074-00-CH	COOK	245	25
CONTRACT NO. 63629				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-CMM-800305U				