

BARRINGTON ROAD - STAGE 2							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
203+03.28		11.3	4.8				
	46.72			12.0	4.4	20.7	7.6
203+50.		12.6	4.0				
	50			13.7	4.7	25.4	8.8
204+00		14.8	5.5				
	50			13.1	4.7	24.3	8.6
204+50		11.4	3.8				
	50			12.9	3.5	23.9	6.5
205+00		14.4	3.3				
	50			16.2	3.4	30.0	6.3
205+50		18.0	3.5				
	50			19.2	3.6	35.6	6.5
206+00		20.5	3.4				
	50			16.7	3.1	31.0	5.8
206+50		13.0	2.8				
	50			21.8	3.4	40.3	6.2
207+00		30.6	4.0				
	50			33.1	4.1	61.3	7.7
207+50		35.7	4.3				
	50			35.7	4.3	66.2	8.0
208+00		35.8	4.3				
	50			35.6	4.4	65.9	8.1
208+50		35.4	4.4				
	50			36.3	4.4	67.2	8.2
209+00		37.1	4.4				
	50			35.1	4.5	64.9	8.2
209+50		33.0	4.5				
	50			40.9	5.7	75.6	10.5
210+00		48.8	6.9				
	50			55.1	6.2	102.1	11.4
210+50		61.5	5.5				
	50			58.8	4.7	108.9	8.7
211+00		56.2	4.0				
	50			70.9	4.0	131.3	7.4
211+50		85.6	4.0				
	50			92.7	4.0	171.7	7.4
212+00		99.8	4.0				
	50			91.3	3.5	169.1	6.4
212+50		82.8	3.0				
	50			69.2	3.0	128.2	5.5
213+00		55.7	3.0				
	50			50.5	3.0	93.5	5.5
213+50		45.3	3.0				
	50			42.2	3.0	78.2	5.5
214+00		39.1	3.0				
	50			34.5	3.4	63.9	6.3
214+50		29.9	3.8				
	50			45.4	4.4	84.0	8.1
215+00		60.8	4.9				
	50			30.4	2.5	56.3	4.5
215+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
216+00		0.0	0.0				
	50			53.9	1.0	99.9	1.9
216+50		107.9	2.0				
	50			88.0	2.5	159.2	4.7
217+00		64.1	3.0				
	50			57.7	3.2	106.9	6.0
217+50		51.3	3.5				
	50			44.1	6.2	81.7	11.5
218+00		36.9	9.0				
	50			36.2	9.8	67.0	18.1

(CONTINUED) BARRINGTON ROAD - STAGE 2							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
218+50.		35.5	10.6				
	50			37.0	9.7	68.5	18.0
219+00.		38.4	8.9				
	50			39.2	7.4	72.6	13.7
219+50.		39.9	5.9				
	50			41.3	5.1	76.5	9.4
220+00.		42.7	4.2				
	50			43.2	4.0	80.1	7.4
220+50.		43.7	3.8				
	50			44.0	3.9	81.5	7.2
221+00.		44.3	4.0				
	50			42.5	3.6	78.7	6.6
221+50.		40.7	3.1				
	50			41.3	3.1	76.5	5.8
222+00.		42.0	3.1				
	50			41.6	3.1	77.0	5.8
222+50.		41.2	3.1				
	50			41.1	4.7	76.0	8.7
223+00.		40.9	6.3				
	50			43.2	4.9	80.0	9.1
223+50.		45.5	3.6				
	50			32.2	3.5	58.5	6.5
224+00.		18.8	3.4				
	50			16.0	3.6	29.7	6.7
224+50.		13.3	3.8				
	50			12.1	3.8	22.4	7.1
225+00.		10.9	3.9				
	50			10.5	3.9	19.4	7.2
225+50.		10.0	3.9				
	50			9.8	3.9	18.1	7.2
226+00.		9.6	4.0				
	50			9.3	3.8	17.2	7.0
226+50.		8.9	3.7				
	50			9.1	3.5	16.8	6.6
227+00.		9.2	3.4				
	50			9.5	3.3	17.5	6.2
227+50.		9.7	3.2				
	50			9.9	3.3	18.3	6.2
228+00.		10.0	3.4				
	50			12.1	3.7	22.4	6.8
228+50.		14.2	3.9				
	50			7.1	2.0	13.2	3.6
229+00.		0.0	0.0				
	50			2.9	3.3	5.3	6.1
229+50.		5.8	6.6				
	50			7.6	5.1	14.1	9.5
230+00.		9.5	3.6				
	50			8.4	3.8	15.6	7.1
230+50.		7.3	4.1				
	50			7.2	4.1	13.4	7.6
231+00.		7.1	4.1				
	50			8.1	4.0	15.0	7.5
231+50.		9.1	3.9				
	50			8.6	3.8	16.0	7.0
232+00.		8.1	3.6				
	50			8.2	3.6	15.2	6.6
232+50.		8.3	3.5				
	50			8.6	3.3	15.9	6.1
233+00.		8.9	3.1				
	50			9.7	3.3	17.9	6.1
233+50.		10.4	3.5				
	28.58			9.8	3.6	10.4	3.8
233+78.58		9.2	3.7				
BARRINGTON ROAD - STAGE 2 TOTAL						3,495.1	456.2

FILE NAME = .../cad/sheet/2329\_5schedule\_02.dgn

USER NAME = djc  
 PLOT SCALE = 50.0000' / 1" = 5/15/2012

DESIGNED - JAT  
 DRAWN - JAT  
 CHECKED - DJK  
 DATE - 8-20-12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 3 OF 9 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074-00-CH	COOK	245	26
CONTRACT NO. 63629				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-CM-8003051				