

SCHAUMBURG ROAD - STAGE 2							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
35+19.5		10.7	3.6				
	30.5			13.1	6.0	14.8	6.8
35+50		15.5	8.5				
	50			10.0	10.3	18.4	19.0
36+00		4.4	12.0				
	50			7.3	10.4	13.5	19.2
36+50		10.2	8.7				
	50			10.4	8.2	19.2	15.1
37+00		10.5	7.6				
	50			10.4	8.1	19.3	15.1
37+50		10.3	8.6				
	50			10.4	7.0	19.2	13.0
38+00		10.4	5.4				
	50			14.4	5.4	26.6	10.0
38+50		18.3	5.4				
	50			16.7	5.3	30.9	9.8
39+00		15.0	5.2				
	50			13.1	5.0	24.2	9.3
39+50		11.2	4.8				
	50			12.8	5.0	23.8	9.2
40+00		14.5	5.1				
	50			11.7	5.0	21.6	9.3
40+50		8.9	5.0				
	50			9.0	5.2	16.7	9.7
41+00		9.1	5.5				
	50			9.1	5.1	16.9	9.5
41+50		9.2	4.8				
	50			21.3	2.4	39.5	4.4
42+00		33.5	0.0				
43+50		81.4	3.4				
	50			62.9	3.8	116.4	7.0
44+00		44.3	4.2				
	50			43.0	4.2	79.6	7.8
44+50		41.7	4.3				
	50			46.1	4.3	85.3	8.0
45+00		50.4	4.3				
	50			47.9	4.3	88.6	8.0
45+50		45.3	4.4				
	50			47.3	4.4	87.6	8.1
46+00		49.4	4.4				
	50			45.5	4.4	84.2	8.1
46+50		41.6	4.4				
	50			42.0	4.4	77.8	8.1
47+00		42.4	4.3				
	50			41.8	4.3	77.5	7.9
47+50		41.3	4.2				
	50			42.2	4.2	78.2	7.8
48+00		43.2	4.2				
	50			27.8	13.5	51.4	25.1
48+50		12.4	22.9				
	50			20.7	15.4	38.4	28.6
49+00		29.1	8.0				
	50			21.7	6.1	40.2	11.3
49+50		14.3	4.2				
	50			15.4	4.1	28.5	7.7
50+00		16.5	4.0				
	50			14.6	4.2	27.1	7.8
50+50		12.8	4.4				
	50			12.2	4.7	22.5	8.8

(CONTINUED) SCHAUMBURG ROAD - STAGE 2							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
51+00.		11.5	5.1				
	50			11.5	5.4	21.3	10.0
51+50.		11.5	5.7				
	50			12.9	5.2	23.9	9.7
52+00.		14.2	4.8				
	50			15.3	4.5	28.3	8.3
52+50.		16.3	4.1				
	50			14.4	3.8	26.7	7.1
53+00.		12.6	3.5				
	40			10.4	4.0	15.4	6.0
53+40.03		6.2	4.6				
SCHAUMBURG ROAD - STAGE 2 TOTAL						1,388.3	354.4

FILE NAME = ... \eod\sheet\2329_Schedule_02.dgn

USER NAME = djc
 PLOT SCALE = 50.0000 / in
 PLOT DATE = 8/16/2012

DESIGNED - JAT
 DRAWN - JAT
 CHECKED - DJK
 DATE - 8-20-12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 7 OF 9 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1322	01-00074+00-CH	COOK	245	30
CONTRACT NO. 63629				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-OMM-8003(05)				