

HOLMES WAY - RECONSTRUCTION							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
299+23.26		54.8	5.7				
	26.74			57.8	5.8	57.2	5.8
299+50		60.8	5.9				
	50			69.8	3.0	129.3	5.5
300+00		78.9	0.0				
	50			78.2	3.0	144.8	5.6
300+50		77.5	6.0				
	50			72.6	6.1	134.5	11.2
301+00		67.8	6.2				
	50			59.0	5.9	109.2	10.9
301+50		50.2	5.7				
	50			46.0	5.5	85.2	10.3
302+00		41.8	5.4				
303+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
303+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
304+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
304+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
305+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
305+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
306+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
306+50		0.0	0.0				
	42.21			0.0	0.0	0.0	0.0
306+92.21		0.0	0.0				
HOLMES WAY RECONSTRUCTION TOTAL						660.2	49.3

HOLMES WAY WIDENING AND RESURFACING							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
299+23.26		0.0	0.0				
	26.74			0.0	0.0	0.0	0.0
299+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
300+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
300+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
301+00		0.0	0.0				
	50			0.0	0.0	0.0	0.0
301+50		0.0	0.0				
	50			0.0	0.0	0.0	0.0
302+00		0.0	0.0				
303+00		0.0	0.0				
	50			17.9	3.8	33.2	7.0
303+50		35.8	7.5				
	50			36.5	7.1	67.6	13.2
304+00		37.2	6.7				
	50			34.5	6.7	64.0	12.4
304+50		31.9	6.7				
	50			26.4	8.8	48.9	16.3
305+00		20.9	10.8				
	50			22.1	11.4	40.9	21.2
305+50		23.2	12.0				
	50			21.3	9.9	39.5	18.3
306+00		19.4	7.7				
	50			18.8	6.8	34.9	12.5
306+50		18.2	5.9				
	42.21			18.0	6.0	28.2	9.4
306+92.21		17.8	6.2				
HOLMES WAY WIDENING AND RESURFACING TOTAL						357.1	110.2

MERIBEL							
STATION	DISTANCE	CUT	FILL	CUT	FILL	CUT	FILL
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. YD.)	(CU. YD.)
10+38.87		27.5	1.3				
	11.13			38.5	2.4	15.9	1.0
10+50		49.4	3.5				
	50			53.1	3.5	98.4	6.5
11+00		56.8	3.5				
	50			94.9	3.2	175.7	5.9
11+50		132.9	2.9				
	18.57			132.9	2.9	91.4	2.0
11+68.57		132.9	2.9				
MERIBEL TOTAL						381.3	15.4
HOLMES WAY - TOTAL						1,041.5	64.7