

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING,

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

FELS NAME = USER NAME = geglianobt DESIGNED - REVISED - R. MIRS 09-15-97	SOTEDIAL BOAD	F.A.U SECTION	COUNTY TOTAL SHEET
VI\distat\22x34\to22.dgn	ARTERIAL ROAD	1322 01-00074-00-CH	COOK 245 193
PLOT SCALE = 50.000 // IN. CHECKED - REVISED -T. RAMMACHER 02-02-99 DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN	TO 22	CONTRACT NO 62620
	OF 1 SHEETS STA. TO STA.	FFD. ROAD DIST. NO. 1 (III INDISEFFD. A	AID PROJECT M-CMM-8003(051)