GENERAL NOTES

- ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE DETAILS IN THE PLANS, THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS, AND THE JANUARY I, 2012 EDITION OF THE FOLLOWING STATE OF ILLINOIS SPECIFICATIONS: "THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (REFERRED TO AS THE "STANDARD SPECIFICATIONS"), THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS", AND THE "MANUAL OF TEST PROCEDURES FOR MATERIALS".
- THE LOCATIONS OF PUBLIC OR PRIVATE UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND THE VILLAGE DOES NOT GUARANTEE THEIR ACCURACY. THE CONTRACTOR SHALL HAVE THE RESPECTIVE UTILITY COMPANIES FIELD LOCATE ALL THEIR FACILITIES PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL ALSO VERIFY THE DEPTHS OF THE EXISTING UTILITIES IF NECESSARY. ANY RELOCATION OR LOWERING OF UTILITIES SHALL BE COORDINATED BY THE
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES, INCLUDING SPRINKLER SYSTEMS, EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY OR SPRINKLER SYSTEM THAT IS DAWAGED DURING CONSTRUCTION SHALL BE REPLACED OR REPLACED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OR DESTRUCTION OF PUBLIC OR PRIVATE UTILITIES, AND SHALL REPAIR ANY UTILITIES AT HIS OR HER OWN EXPENSE. COORDINATION OF ALL UTILITY WORK INVOLVED IN THE CONSTRUCTION AREA WILL BE DISCUSSED AT A PRECONSTRUCTION COMFERENCE. THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF ANY UTILITY
- 5. THE CONTRACTOR SHALL NOTIFY THE VILLAGE PUBLIC WORKS ADMINISTRATOR 847-671-8252 AT LEAST 48 HOURS IN ADVANCE OF BEGINNING WORK TO OBTAIN VILLAGE UTILITY LOCATIONS AND SHALL COORDINATE ALL CONSTRUCTION OPERATIONS WITH THE ENGINEER.
- DURING CONSTRUCTION STAGING OPERATIONS, THE FRANKLIN PARK POLICE 847-671-8203 AND FIRE 847-671-4800 DEPARTMENTS SHALL BE NOTIFIED IN WRITING 48 HOURS PRIOR TO LANE CLOSURES. EMERGENCY ACCESS SHALL BE MAINTAINED AND ALLOWED AT ALL TIMES. NO OVERNIGHT LANE CLOSURES WILL
- 7. MATERIALS RESULTING FROM THE REMOVAL OF PAVEMENT, SIDEWALK, CURB AND GUTTER, HOT-MIX ASPHALT SURFACES, ETC. SHALL BE REMOVED AT THE END OF EACH DAY TO AN APPROVED SITE. IN THE JUDGMENT OF THE ENGINEER, SHOULD IT BE NECESSARY TO REMOVE SUCH MATERIALS, THE ENGINEER WILL HAVE THE MATERIAL REMOVED AND THE CONTRACTOR WILL BE BILLED (CHARGED) ACCORDINGLY.
- THE CONTRACTOR MAY OBTAIN MUNICIPAL WATER IN BULK, AT NO CHARGE, AS LONG AS THERE IS NOT A "WATERING BAN" IN EFFECT. THE INDISCRIMINATE USE OF FIRE HYDRANTS IS STRICTLY PROHIBITED. WATER FOR CONSTRUCTION SHALL BE METERED OR OTHERWISE ACCOUNTED FOR AND A DAILY LOG MAINTAINED. THE CONTRACTOR SHALL PROVIDE THE WATER TRUCK AND DRIVER REQUIRED TO OBTAIN AND TRANSPORT THIS WATER. THE VILLAGE RESERVED THE RIGHT TO RESTRICT OR REFUSE THE USE OF VILLAGE WATER IF DEEMED NECESSARY. THIS WORK WILL BE INCLUDED IN THE SUPPLEMENTAL WATER PAY
- IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE SCHOOLS, RESIDENTS AND THE VILLACE WHEN ACCESS WILL BE TEMPORARILY CLOSED DUE TO CURB AND GUTTER AND/OR SIDEWALK REPLACEMENT. THE CONTRACTOR SHALL DISTRIBLITE NOTICES PROVIDED BY THE VILLAGE TO RESIDENTS. EVERY EFFORT SHALL BE MADE TO ACCOMMODATE ACCESS TO THESE PROPERTIES INCLUDING KNOCKING ON DOORS WHEN SIDEWALK IS ABOUT TO BE CLOSED.

847-451-3000 847-678-7962 847-455-2150

EAST LEYDEN HIGH SCHOOL NORTH ELEMENTARY SCHOOL VANCE C. HESTER JUNIOR HIGH SCHOOL

- 10. THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED. ONE (1) WEIGHTED SANDBAG SHALL BE PLACED ACROSS EACH BOTTOM RAIL.
- 11. THE CONTRACTOR SHALL CONTACT THE LOCAL AGENCY MATERIAL INSPECTOR AT LEAST 48 HOURS PRIOR TO ANY CONCRETE OR HOT-MIX ASPHALT MATERIAL DELIVERIES.
- 12. A PORTABLE BATHROOM(S) SHALL BE PLACED ON THE JOB SITE(S) AND RELOCATED WHEN NECESSARY SO IT IS ACCESSIBLE TO WORKERS, IF WORK IS OCCURRING AT SEVERAL LOCATIONS, ONE PORTABLE BATHROOM SHALL BE PLACED AT EACH LOCATION WITHIN A REASONABLE DISTANCE FROM THE WORK AS DETERMINED BY THE ENGINEER. THIS SHALL BE INCLUDED IN THE PAY ITEM
- FOR STEEL BARS CERTIFICATION, PLEASE CONTACT IDOT BUREAU OF MATERIALS AT (847) 705-4337.
- 14. ANY SIGNS OR MAILBOXES THAT ARE IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED AND REPLACED IN ACCORDANCE WITH VILLAGE STANDARDS AND INCLUDED IN THE PAY ITEM FOR MOBILIZATION. MAIL SERVICE SHALL BE MAINTAINED AT ALL TIMES.
- 15. THE CONTRACTOR SHALL UTILIZE A MECHANICAL SWEEPER TO CLEAN STREETS AFFECTED BY THE CONTRACTOR'S OPERATIONS, INCLUDING HAUL ROUTES, AT LEAST TWICE PER WEEK AND ADDITIONALLY AS DETERMINED BY THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE MOBILIZATION PAY ITEM.
- 16. ANY EXISTING SIGNS TO BE REMOVED SHALL BE DELIVERED TO THE VILLAGE PUBLIC WORKS. REMOVAL AND DELIVERY SHALL BE INCLUDED IN THE REPLACEMENT SIGN PAY ITEM.
- 17. A VERTICAL REFLECTIVE STRIP SHALL BE ADDED TO ALL NEW SIGNACE POSTS AND SUPPORTS AS APPLICABLE. THE COST OF THE STRIP SHALL BE INCLUDED IN THE NEW SIGN PAY ITEM.

HIGHWAY STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-05	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-03	SIGN PANEL ERECTION DETAILS
720021-02	SIGN PANELS EXTRUDED ALUMINUM TYPE

BENCHMARKS

- BM 1 FLANGE BOLT ON FIRE HYDRANT AT THE NORTHWEST CORNER OF 25TH AVENUE AND CHESTNUT AVENUE ELEVATION 643.02 (NAVD 88)
- BM 2 FLANGE BOLT ON FIRE HYDRANT AT NORTHEAST CORNER OF 25TH AVENUE AND GAGE AVENUE ELEVATION 638.06 (NAVD 88)
- BM 3 FLANGE BOLT ON FIRE HYDRANT AT SOUTHWEST CORNER OF 25TH AVENUE AND KING STREET ELEVATION 636.60 (NAVD 88)
- FLANCE BOLT OF FIRE HYDRANT (APPROXIMATELY STA 136+10 \pm RT) ON THE EAST SIDE OF 25TH AVENUE ELEVATION 637.83 (NAVD 88)

INDEX OF SHEETS

TITLE	SHEET
TILL	NO.
COVER SHEET	1
GENERAL NOTES, HIGHWAY STANDARDS, BENCHMARKS AND INDEX OF SHEETS	2
SUMMARY OF QUANTITIES	3
TYPICAL SECTIONS	4
PLAN - 25TH AVENUE	5
DISTRICT ONE DETAIL - TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)	6
DISTRICT ONE DETAIL - ARTERIAL ROAD INFORMATION SIGNING (TC-22)	7

DESIGNED - MWP REVISED REVISED DRAWN C.JC CHECKED LDH REVISED FJLE - 110912-gen-note.sht - 12/03/12

VILLAGE OF FRANKLIN PARK, ILLINOIS 25TH AVENUE 2012 SAFE ROUTES TO SCHOOLS

GENERAL NOTES, HIGHWAY STANDARDS. **BENCHMARKS AND INDEX OF SHEETS**

SCA. F. NONE

COUNTY TOTAL SHEETS NO. SEC1ION CB-00068-00-SW COOK CONTRACT NO. 63719 C-91-347-;2 FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT SRTS-4009(15)

a 2012. E. NOIS C. 184-4