


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE	CONST. CODE
				80% FED	100% OAK PARK
				20% OAK PARK	SAFETY
				0031	0031
				URBAN	URBAN
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	65	65	
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	20	20	
28000510	INLET FILTERS	EACH	4	4	
Δ 31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	400	400	
42001300	PROTECTIVE COAT	SQ YD	400	400	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,750	1,750	
42400800	DETECTABLE WARNINGS	SQ FT	64	64	
44000100	PAVEMENT REMOVAL	SQ YD	186	186	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	92	92	
44000600	SIDEWALK REMOVAL	SQ FT	675	675	
Δ * 50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1		1
* 50606702	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 2	L SUM	1		1
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	

\* SPECIALTY ITEM

FILE NAME = S:\JDL\67408-477916\B4\B12\11-00253-00-Sheets\0163722-11-00.dgn



USER NAME = demtaw	DESIGNED - JDM	REVISED -
PLOT SCALE = 1/8" = 1' IN.	DRAWN - JKP	REVISED -
PLOT DATE = 1/4/2013	CHECKED - MFC	REVISED -
	DATE - 05-07-2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2783	11-00253-00-LS	COCK	25	3
CONTRACT NO. 63722			ILLINOIS FED. AID PROJECT	