

**SUMMARY OF QUANTITIES**

Specialty Item	SP REQ'D (Y/N)	PAY ITEM No.	Description	Unit	Total Quantity	Roadway 0003	Landscaping 0031	Drainage 0044	Traffic Signals 0021	Non-Participating Items
*	N	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	373	--	373	--	--	--
*	N	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	690	--	666	--	--	24
	Y	20101000	TEMPORARY FENCE	FOOT	915	--	761	--	--	154
*	N	20101100	TREE TRUNK PROTECTION	EACH	20	--	17	--	--	3
*	N	20101200	TREE ROOT PRUNING	EACH	15	--	12	--	--	3
*	N	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	6	--	5	--	--	1
*	N	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	12	--	10	--	--	2
*	N	20101700	SUPPLEMENTAL WATERING	UNIT	5	--	3	--	--	2
	N	20200100	EARTH EXCAVATION	CU YD	8324	5657	--	--	--	2667
	N	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20053	18490	--	55	--	1508
	Y	20800150	TRENCH BACKFILL	CU YD	1731	390	--	1273	--	68
	N	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	24555	20382	--	55	--	4138
*	N	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	26730	--	21195	--	--	5535
*	N	21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	7533	--	--	--	--	7533
	Y	21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	300	300	--	--	--	--
*	N	25000210	SEEDING, CLASS 2A	ACRE	5.57	--	4.57	--	--	1
*	Y	25000314	SEEDING, CLASS 4B	ACRE	1.16	--	0.16	--	--	1
*	N	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	600	--	498	--	--	102
*	N	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	191	--	191	--	--	--
*	N	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	600	--	498	--	--	102
*	N	25100115	MULCH, METHOD 2	ACRE	5.47	--	4.47	--	--	1
*	N	25100630	EROSION CONTROL BLANKET	SQ YD	19350	--	16090	--	--	3260
*	N	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	3750	--	3118	--	--	632
*	N	25200110	SODDING, SALT TOLERANT	SQ YD	6808	--	5661	--	--	1147
*	N	25200200	SUPPLEMENTAL WATERING	UNIT	25	--	21	--	--	4
	N	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	120	--	100	--	--	20
*	N	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	685	--	514	--	--	171
	Y	28000305	TEMPORARY DITCH CHECKS	FOOT	1220	--	1014	--	--	206
	Y	28000400	PERIMETER EROSION BARRIER	FOOT	5292	--	4400	--	--	892
	N	28000510	INLET FILTERS	EACH	85	--	83	--	--	2
	N	28100105	STONE RIPRAP, CLASS A3	SQ YD	100	--	83	--	--	17
	Y (D1)	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	7452	6570	--	55	--	827
	Y (D1)	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	51815	44505	--	--	--	7310
	N	35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	82	82	--	--	--	--
	N	35101400	AGGREGATE BASE COURSE, TYPE B	TON	4	--	--	--	--	4
	N	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	4041	3360	--	--	--	681
	N	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	23280	20355	--	--	--	2925
	N	40600300	AGGREGATE (PRIME COAT)	TON	134	117	--	--	--	17
	N	40600895	CONSTRUCTING TEST STRIP	EACH	4	3	--	--	--	1
	N	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	350	215	--	--	--	135
	N	40600990	TEMPORARY RAMP	SQ YD	400	333	--	--	--	67
	N	40603050	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1247	1037	--	--	--	210
	N	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1728	1437	--	--	--	291

Specialty Item	SP REQ'D (Y/N)	PAY ITEM No.	Description	Unit	Total Quantity	Roadway 0003	Landscaping 0031	Drainage 0044	Traffic Signals 0021	Non-Participating Items
	N	40701876	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 3/4"	SQ YD	29450	21957	--	--	--	7493
	N	40701888	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/4"	SQ YD	18370	18370	--	--	--	--
	N	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	40	33	--	--	--	7
	N	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	342	75	--	--	--	267
	N	42400800	DETECTABLE WARNINGS	SQ FT	73	--	--	--	--	73
	N	44000100	PAVEMENT REMOVAL	SQ YD	47247	41712	--	--	--	5535
	N	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3772	3382	--	--	--	390
	N	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2160	2160	--	--	--	--
	N	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	560	466	--	--	--	94
	N	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	560	466	--	--	--	94
	N	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	560	466	--	--	--	94
	N	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	560	466	--	--	--	94
	N	44213200	SAW CUTS	FOOT	3000	2494	--	--	--	506
	N	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5153	4546	--	--	--	607
	N	48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	826	826	--	--	--	--
	N	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1776	1776	--	--	--	--
	N	48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	1439	1439	--	--	--	--
	N	50104400	CONCRETE HEADWALL REMOVAL	EACH	69	--	--	57	--	12
	N	50105220	PIPE CULVERT REMOVAL	FOOT	1943	--	--	1472	--	471
	N	50300225	CONCRETE STRUCTURES	CU YD	39	--	--	39.0	--	--
	N	50300300	PROTECTIVE COAT	SQ YD	2000	--	--	2000	--	--
	N	50800105	REINFORCEMENT BARS	POUND	2580	--	--	2580	--	--
	N	542A0211	PIPE CULVERTS, CLASS A, TYPE 1 6"	FOOT	2	--	--	2	--	--
	N	542A0215	PIPE CULVERTS, CLASS A, TYPE 1 10"	FOOT	6	--	--	6	--	--
	N	542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	188	--	--	188	--	--
	N	542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	222	--	--	162	--	60
	N	542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	174	--	--	174	--	--
	N	542A5470	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	20	--	--	0	--	20
	N	542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	130	--	--	60	--	70
	N	5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12"(TEMPORARY)	FOOT	109	--	--	89	--	20
	N	5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15"(TEMPORARY)	FOOT	376	--	--	306	--	70
	N	5421D036	PIPE CULVERTS, CLASS D, TYPE 1 36"(TEMPORARY)	FOOT	42	--	--	42	--	--
	N	54213655	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 10"	EACH	2	--	--	2	--	--
	N	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	--	--	1	--	--
	N	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	13	--	--	13	--	--
	N	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	13	--	--	11	--	2
	N	54213659	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	--	--	6	--	--
	N	54214500	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	2	--	--	0	--	2
	N	54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	4	--	--	2	--	2
	N	54260311	TRAVERSABLE PIPE GRATE	FOOT	119	--	--	119	--	--
	N	54261330	CONCRETE END SECTION, STANDARD 542001, 30", 1:3	EACH	2	--	--	2	--	--
	N	54261336	CONCRETE END SECTION, STANDARD 542001, 36", 1:3	EACH	6	--	--	6	--	--
	N	54261442	CONCRETE END SECTION, STANDARD 542001, 42", 1:4	EACH	1	--	--	1	--	--

FILE NAME: N:\LIC\2013\4222\CONV\11\0109\_042229\_01.SHT  
 USER NAME: pmagnelli  
 PLOT SCALE: 1"  
 PLOT DATE: 2/6/2013

DESIGNED: -  
 DRAWN: -  
 CHECKED: -  
 DATE: -  
 REVISED: -  
 REVISED: -  
 REVISED: -  
 REVISED: -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**WADSWORTH ROAD AT GREEN BAY ROAD  
 SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 1209	SECTION 03-00033-12-CH	COUNTY LAKE	TOTAL SHEETS 189	SHEET NO. 5
CONTRACT NO. 63766				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				