NOTE: THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

MATCH LINE STA. 204+00

MATCH LINE STA. 210+00

04-31-116-013
BANK OF WAUKEGAN TRUST

04-31-108-002
04-31-114-004
JOHNSON

04-31-115-002
04-31-115-003
04-31-115-004
OTTERBACHER

04-31-115-001
IFTIMIE

TEMP. CONSTRUCTION EASEMENT

PROP. R.O.W.

EX. R.O.W.

HMA SHOULDER, 6"

HMA SHOULDER, 10"

GUTTER OUTLET, TYPE A

GUTTER OUTLET, TYPE A

45:1 TAPER

℄ IL RTE 131

(UNIMPROVED)

PICKFORD STREET
(UNIMPROVED)

SCALE IN FEET

LEGEND
- EXISTING RIGHT OF WAY
- PROPOSED RIGHT OF WAY
- EXISTING PERMANENT EASEMENT
- TEMPORARY EASEMENT
- PROPOSED PERMANENT EASEMENT
- WETLAND

250.00' V.C.
K = 152.30
e = 0.51'
LOW POINT STA. 205+45.09
ELEVATION 726.44

VPC STA. 204+99.40
ELEVATION 726.51

VPI STA. 206+24.40
ELEVATION 726.13

VPI STA. 207+49.40
ELEVATION 727.81

300.00' V.C.
K = 148.04
e = 0.76

-0.30%
-0.30%
+1.34%
+1.34%

726.66 726.80 | 726.48 726.65 | 726.35 726.50 | 726.30 726.44 | 726.44 726.54 | 726.65 726.80 | 727.09 727.22 | 727.57 727.81 | 728.37 728.49 | 729.11 729.17 | 729.88 729.83 | 730.57 730.50 | 731.07 731.09

204+00 204+50 205+00 205+50 206+00 206+50 207+00 207+50 208+00 208+50 209+00 209+50 210+00

FILE NAME = N:\ILDOT\84229\Civil\RPP_RTE131_02.SHT	USER NAME = nmarel	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20'	CHECKED -	REVISED -
	PLOT DATE = 1/22/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE 131 (GREEN BAY ROAD)
ROADWAY PLAN AND PROFILE
STA. 204+00.00 TO STA. 210+00.00

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1209	03-00033-12-CH	LAKE	189	40
		CONTRACT NO. 63766		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		