



SCALE 1" = 20'

**B-10**

	N	M%	Qu
FILL - Gravel Shoulder	4	15.7	1.75*
FILL - Blk CLAY LOAM, trace br clay, moist A-6	8	16.6	0.75*
Med. stiff br & gr LOAM, trace gravel, v. moist (CL) A-4(3) LULPI=21/11/10	12	17.2	2.75*
Very stiff br CLAY, trace gravel, moist (CL) A-6	10	16.8	3.75*
Hard br and gr CLAY, trace gravel, moist (CL) A-6	16	14.7	4.5+*

**B-11**

	N	M%	Qu
FILL - Gravel Shoulder	11	25.9	2.0*
FILL - Black CLAY LOAM, moist A-6	2	30.9	1.0*
Medium stiff to stiff br, gr and black CLAY, trace organic, v. moist A-7-6	1	38.7	0.26*
Very soft black and gr CLAY, trace organic, very moist A-7-6	10	17.5	2.0*
Stiff to v. stiff br and gr CLAY, trace gravel, moist	13	16.4	2.5*
V. stiff gr CLAY, trace gravel, moist A-6			

**LEGEND**  
 BORING LOCATIONS L-62,012 / JULY 2005  
 CORE LOCATIONS L-62,012 / MARCH 2009

**BORING LOCATION PLAN**  
**WADSWORTH & GREEN BAY ROADS**  
 ILLINOIS ROUTE 131  
 LAKE COUNTY, ILLINOIS

**TSC** TESTING SERVICE CORPORATION  
 457 EAST GUNDERSEN DRIVE  
 CAROL STREAM, ILLINOIS 60188

DRAWN BY: TRP  
 CHECKED BY: MVM  
 JOB NO.: L-62,012A  
 DATE: 12-10-10

PAGE NO. 4 OF 11

FILE NAME =	USER NAME =	DESIGNED =	REVISED =
R:\L\CDT\B4229\CD\WADSWORTH_04229_04.SHT	mimo-dj		
		DRAWN =	REVISED =
		CHECKED =	REVISED =
		DATE =	REVISED =

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**WADSWORTH ROAD AT GREEN BAY ROAD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS
1209	03-00033-12-CH	LAKE	189 / 137
CONTRACT NO. 63766			
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			