



LEGEND

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)
- PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT
- PROPOSED UTILITY POLE (BY OTHERS)
- PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- PROPOSED HANDHOLE PER LATEST DOT STD 8400
- PROPOSED UNIT DUCT, 600V, 2-1/2" NO.6, 1/2" NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
- PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED
- PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED

NOTES:

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.
2. SEE "HANDHOLE, COMPOSITE CONCRETE" SPECIAL PROVISION FOR HANDHOLE SIZES.

<p>CMT CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-023613</p>	MODEL NAME = Detail	DESIGNED - JWD	REVISED -	2/22/2013
	FILE NAME = 020421-001.dwg	DRAWN - JWD	REVISED -	
	PLOT SCALE = 48,0000 / in.	CHECKED - AB	REVISED -	
	PLOT DATE = 2/22/2013 - 3:45:13 PM	DATE - 11/02/2012	REVISED -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN
IL RTE 2 (SOUTH MAIN STREET)**

SCALE: 1" = 20' SHEET 10 OF 32 SHEETS STA. 392+00 TO STA. 398+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	496
CONTRACT NO. 64821				ILLINOIS FED. AID PROJECT

DIRECTORY: I:\PROJECTS\115606\DWG\Drawings\Sheet\496.dwg
 USER: JWD
 DATE: 2/22/2013 3:45:13 PM