



**LEGEND**

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)
- PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT
- ⊕ PROPOSED UTILITY POLE (BY OTHERS)
- ⊞ PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- ⊞ HH = PROPOSED HANDHOLE PER LATEST DOT STD 814001
- ⊞ CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- ⊞ PROPOSED JUNCTION BOX
- ⊞ PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED
- ⊞ PROPOSED UNIT DUCT, 600V, 2-1/2" NO.6, 1/2" NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- ⊞ PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
- ⊞ PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

**NOTES:**

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.

**CMT**  
CRAWFORD, MURPHY & TILLY, INC.  
CONSULTING ENGINEERS  
LEADER No. 184-200813

MODEL NAME = Detail	DESIGNED - JWD	REVISED -	2/22/2013
FILE NAME = 02401-0482111.dgn	DRAWN - JWD	REVISED -	
PLOT SCALE = 48.0000 / 1 in.	CHECKED - AB	REVISED -	
PLOT DATE = 2/22/2013 3:45:16 PM	DATE - 11/02/2012	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN  
IL RTE 2 (SOUTH MAIN STREET)**

SCALE: 1" = 20' SHEET 11 OF 32 SHEETS STA. 398+00 TO STA. 404+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	497
CONTRACT NO. 64821			[ILLINOIS] FED. AID PROJECT	

DIRECTOR: J. L. ... USER NAME: J. Jason Dove