



LEGEND

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)
- PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT
- ◆ PROPOSED UTILITY POLE (BY OTHERS)
- PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- ⊠ HH = PROPOSED HANDHOLE PER LATEST DOT STD 8.400
- ⊠ CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- PROPOSED JUNCTION BOX
- PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED
- PROPOSED UNIT DUCT, 600V, 2-1/2" NO.6, 1/2" NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- FO — PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
- — — — — PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

NOTES:

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.
2. SEE "HANDHOLE, COMPOSITE CONCRETE" SPECIAL PROVISION FOR HANDHOLE SIZES.

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
LICENSE NO. 164-000613

MODEL NAME = Dwg.dwg	DESIGNED - JWD	REVISED - 2/22/2013
FILE NAME = 0264821-001.rvt	DRAWN - JWD	REVISED -
PLOT SCALE = 48.0000 / 1 in.	CHECKED - AB	REVISED -
PLOT DATE = 2/22/2013 - 3:45:24 PM	DATE - 11/02/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY LIGHTING PLAN
IL RTE 2 (SOUTH MAIN STREET)
SCALE: 1" = 20' SHEET 13 OF 32 SHEETS STA. 410+00 TO STA. 416+00

F.A.P. RTE. 742	SECTION (32, 33) R-1	COUNTY WINNEBAGO	TOTAL SHEETS 705	SHEET NO. 499
CONTRACT NO. 64821				ILLINOIS FED. AID PROJECT

DIRECTORY: L:\WORK\0264821\001\Drawings\0264821.dwg
 USER NAME: j.tilley Date: