



**LEGEND**

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 487)
- PROPOSED UNDERPASS LUMINAIRE, METAL HALIDE, VERTICAL MOUNT, 100 WATT
- PROPOSED UTILITY POLE (BY OTHERS)
- PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- HH = PROPOSED HANDHOLE PER LATEST DOT STD 8400
- CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- PROPOSED JUNCTION BOX
- PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AND CONDUCTORS AS INDICATED
- PROPOSED UNIT DUCT, 600V, 2-1/2 NO.6, 1/2 NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- FO — PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER CABLE
- PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

**NOTES:**

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 487.
2. SEE "HANDHOLE, COMPOSITE CONCRETE" SPECIAL PROVISION FOR HANDHOLE SIZES.

MODEL NAME : Detail	DESIGNED - JWD	REVISED -	2/22/2013
FILE NAME : D:\64821-00\light17.dgn	DRAWN - JWD	REVISED -	
PLOT SCALE : 48.0000 / 1 in.	CHECKED - AB	REVISED -	
PLOT DATE : 2/22/2013 - 3:45:44 PM	DATE - 11/02/2012	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN  
IL RTE 2 (SOUTH MAIN STREET)**

SCALE: 1" = 20'    SHEET 17 OF 32 SHEETS    STA. 432+00 TO STA. 438+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	(32, 33) R-1	WINNEBAGO	705	503
CONTRACT NO. 64821			ILLINOIS FED. AID PROJECT	

DIRECTORY : C:\PROGRA~1\AutoCAD\Shelton\64821.dwg  
 USER NAME : Jason Dore

