

BRIDGE
037-0048

DOLIBLE
BOX

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ACRS		ACHSIP	ACRS
				80% FED 20% STATE 0040	80% FED 20% STATE 0011	90% FED 10% STATE 0021	80% FED 20% STATE 0011
				QUANTITY	QUANTITY	QUANTITY	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,183	1,183			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2,042	791		1,251	
20101000	TEMPORARY FENCE	FOOT	183	183			
20200100	EARTH EXCAVATION	CU YD	30,195	30,195			
20300100	CHANNEL EXCAVATION	CU YD	750	750			
* 25000210	SEEDING, CLASS 2A	ACRE	5.5	5.5			
* 25000310	SEEDING, CLASS 4	ACRE	6.25	6.25			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,125	1,125			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,125	1,125			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,125	1,125			
Δ 25000750	MOWING	ACRE	5.5	5.5			
* 25100125	MULCH, METHOD 3	ACRE	8.25	8.25			
* 25100630	EROSION CONTROL BLANKET	SQ YD	4,350	4,350			
* 25100900	TURF REINFORCEMENT MAT	SQ YD	2,110	2,110			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,000	4,000			
28000305	TEMPORARY DITCH CHECKS	FOOT	1,390	1,390			
28000400	PERIMETER EROSION BARRIER	FOOT	660	660			
28000500	INLET & PIPE PROTECTION	EACH	14	14			
28100105	STONE RIPRAP, CLASS A3	SQ YD	2,474	2,474			
28100107	STONE RIPRAP, CLASS A4	SQ YD	452	452			
28100109	STONE RIPRAP, CLASS A5	SQ YD	594		594		
28100205	STONE RIPRAP, CLASS A3	TON	638	638			
28200200	FILTER FABRIC	SQ YD	3,835	3,241	594		

* SPECIALTY ITEMS
Δ 100% STATE

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
C:\pvc\work\pvidot\cushmanba\4816\1166\1028039\sh1\shadula.dgn	hoganenjd	DRAWN -	REVISED -
PLOT SCALE * 1/8"=1'-0"		CHECKED -	REVISED -
PLOT DATE * Wed Oct 24 11:12:44 2012		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
226	31 & 3DR-1	HENRY	210	2
CONTRACT NO. 64F25				
ILLINOIS FED. AID PROJECT				

Rev.