

SCHEDULE OF QUANTITIES

60100915 PIPE DRAINS 6"

FOOT	LOCATION
	US 20
<u>20.0</u>	As Needed & Directed by the Resident Engineer
20.0	TOTAL

60107600 PIPE UNDERDRAINS 4"

FOOT	LOCATION
	US 20
<u>110.0</u>	Sta 876 + 03
110.0	TOTAL

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION
	US 20
<u>75.0</u>	Sta 876 + 10 - 876 + 85
75.0	TOTAL

61101009 STORM SEWERS PROTECTED CLASS A 8"

FOOT	LOCATION
	US 20
<u>100.0</u>	As Needed & Directed by the Resident Engineer
100.0	TOTAL

61133100 FIELD TILE JUNCTION VAULTS 2' DIA.

EACH	LOCATION
	US 20
<u>2.0</u>	As Needed & Directed by the Resident Engineer
2.0	TOTAL

63500105 DELINEATORS

EACH	LOCATION
	US 20
1.0	Sta 876 + 27 RT
1.0	Sta 876 + 89 LT
1.0	Sta 878 + 51 RT
1.0	Sta 878 + 51 LT
1.0	Sta 881 + 02 RT
1.0	Sta 881 + 02 LT
<u>6.0</u>	TOTAL

66700305 PERMANENT SURVEY MARKERS TYPE II

EACH	LOCATION
	US 20
<u>1.0</u>	As Directed by the Resident and Coordination with Surveys
1.0	TOTAL

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

EACH	LOCATION
	US 20
<u>1.0</u>	As Needed & Directed by the Resident Engineer Stage I and Stage II
1.0	As Needed & Directed by the Resident Engineer Stage II
1.0	TOTAL

70106700 TEMPORARY RUMBLE STRIPS

EACH	LOCATION
	US 20
<u>12.0</u>	As required per Standard 701321
12.0	TOTAL

70300100 SHORT TERM PAVEMENT MARKING

FOOT	LOCATION
	US 20
50.0	Sta 869 + 75 - 882 + 25 White Shoulder LT
50.0	Sta 869 + 75 - 882 + 25 White Shoulder RT
<u>120.0</u>	Sta 869 + 75 - 882 + 25 Yellow Centerline
220.0	TOTAL

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
	US 20
645.0	Sta 869 + 58 - 882 + 90 Stage I RT
511.0	Sta 869 + 58 - 874 + 69 Stage I C
365.0	Sta 879 + 25 - 882 + 90 Stage I C
1047.0	Sta 872 + 42 - 882 + 90 Stage I LT
899.0	Sta 870 + 95 - 879 + 94 Stage II RT
274.0	Sta 870 + 95 - 873 + 69 Stage II C
274.0	Sta 879 + 37 - 882 + 11 Stage II C
<u>1116.0</u>	Sta 870 + 95 - 882 + 11 Stage II LT
4857.0	TOTAL

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
	US 20
12.0	Sta 873 + 70 Stage I
12.0	Sta 879 + 25 Stage I
12.0	Sta 873 + 68 Stage II
<u>12.0</u>	Sta 879 + 37 Stage II
48.0	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	US 20
17.0	Sta 869 + 75 - 882 + 25 White Shoulder LT
17.0	Sta 869 + 75 - 882 + 25 White Shoulder RT
40.0	Sta 869 + 75 - 882 + 25 Yellow Centerline
213.0	Sta 869 + 58 - 882 + 90 Stage I RT
169.0	Sta 869 + 58 - 874 + 69 Stage I C
121.0	Sta 879 + 25 - 882 + 90 Stage I C
346.0	Sta 872 + 42 - 882 + 90 Stage I LT
297.0	Sta 870 + 95 - 879 + 94 Stage II RT
91.0	Sta 870 + 95 - 873 + 69 Stage II C
91.0	Sta 879 + 37 - 882 + 11 Stage II C
368.0	Sta 870 + 95 - 882 + 11 Stage II LT
4.0	Sta 873 + 70 Stage I
4.0	Sta 879 + 25 Stage I
4.0	Sta 873 + 68 Stage II
<u>4.0</u>	Sta 879 + 37 Stage II
1786.0	TOTAL

Rev. 2-20-13

FILE NAME :	USER NAME : hardnestb-	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 20 /IL 84 SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			301	29T-2	JO DAVIESS	52	12	
		CHECKED -	REVISED -			CONTRACT NO. 64H17					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
PLOT SCALE : 88.8888' / in.				SCALE:		SHEET OF SHEETS		STA. TO STA.			
PLOT DATE : Mon Dec 18 14:06:31 2012											