

# SUMMARY OF QUANTITIES

80% FEDERAL  
20% STATE  
0040

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
48203019	HOT- MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1,197
50100300	REMOVAL OF EXISTING STRUCTURE NO. 1	EACH	1
50800205	REINFORCEMENT BAR, EPOXY COATED	POUND	8,600
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	46.9
54011005	PRECAST CONCRETE BOX CULVERTS 10' X 5'	FOOT	114
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	67
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"	EACH	1
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2
60100915	PIPE DRAINS 6"	FOOT	20
60107600	PIPE UNDERDRAINS 4"	FOOT	110
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	75
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	100
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
63500105	DELINEATORS	EACH	6
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1

\* SPECIALTY ITME  
\*\*\* NON- PARTICIPATING 100%

FILE NAME :	USER NAME : hardnestbr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>US 20 / IL 84 SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\hardnestbr\0277919\020711-shl-500.dgn	DRAWN -	REVISED -	301			291-2	JO DAVIESS	52	6	
PLOT SCALE * 08.0000 / in	CHECKED -	REVISED -	CONTRACT NO. 64H17							
PLOT DATE * Mon Dec 10 14:55:53 2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.