



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 22, 2013

SUBJECT: FAI Route 57(I-57)
Project NHPP-057-6(194)297
Section 141BR (SB) & 38-1BR(NB)
Iroquois County
Contract No. 66944
Item No. 88, March 8, 2013 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Page iii of the Table of Contents to the Special Provisions.
2. Added Page 172 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P. E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Paul Loete, Region 2, District 3; Mike Renner; D. Carl Puzey; Estimates

dp

TEMPORARY CONSTRUCTION/WATERWAY PERMITS (CORPS OF ENGINEERS)

(Effective January 1, 2001; Revised January 1, 2002)

Temporary in-stream work for proposed construction activities has been authorized from the Army Corps of Engineers using the following guidelines:

All requests made by the Contractor shall refer to Permit No. **CEMVR-OD-P-2012-1805** for Structure Number: **038-0015 & 038-0016 (Exist)/ 038-0215 & 038-0216 (Prop)**

Temporary causeway/workpad:

- Area: \pm 1012 sq. yd.
- Location: Actual location to be determined in the field to suit actual construction needs.
- Material Type: Clean coarse aggregates.
- Additional Restrictions: Dewatering methods will be at the option of the contractor. The stream channel within the right-of-way limits must be cleaned and all temporary instream works shall be removed from the stream channel and taken to an upland site upon completion of the project

Should the Contractor desire to deviate from the guidelines currently imposed under the permit as listed above, then full design details including location, material specifications, and hydraulic analysis should be included in a request to the Army Corps of Engineers. Requests shall be made to United States Army Corps of Engineers, Rock Island District, Clock Tower Building, Rock Island, IL 61204.

Any additional request is at the discretion of the Contractor; therefore, any delays in receiving approval for various methods outside of the given parameters will **not** be cause for additional compensation.

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 152
PROJECT LABOR AGREEMENT - QUARTERLY EMPLOYMENT REPORT 156
PROJECT LABOR AGREEMENT 157
TEMPORARY CONSTRUCTION/WATERWAY PERMITS (CORPS OF ENGINEERS) 172