



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 28, 2013

SUBJECT: FAP Route 71(IL 54)
Section (113-RB)I
Ford County
Contract No. 66C52
Item No. 14, March 8, 2013 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Table of Contents – page i.
2. Added page 108 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P. E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Paul Loete, Region 2, District 3; Mike Renner; D. Carl Puzey, Estimates

dp

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	1
KEEPING ROADS OPEN TO TRAFFIC	2
WORK ZONE PAVEMENT MARKING REMOVAL	2
TEMPORARY BRIDGE TRAFFIC SIGNALS (STANDARD 701321)	3
CONCRETE REMOVAL	5
PIPE UNDERDRAINS FOR STRUCTURES	6
RETAINING WALL REMOVAL	6
GRANULAR BACKFILL FOR STRUCTURES	7
RESTORATION OF WORK AREA	8
TEMPORARY CONSTRUCTION/WATERWAY PERMITS (CORPS OF ENGINEERS)	8
404 PERMIT	9
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	13
FRICTION AGGREGATE (BDE)	21
GRANULAR MATERIALS (BDE)	24
PAYMENTS TO SUBCONTRACTORS (BDE)	24
PLACING AND CONSOLIDATING CONCRETE (BDE)	25
PORTLAND CEMENT CONCRETE (BDE)	28
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE)	67
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)	83
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	92
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)	96
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	96
TEMPORARY EROSION AND SEDIMENT CONTROL (BDE)	97
TRACKING THE USE OF PESTICIDES (BDE)	97
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	97
UTILITY COORDINATION AND CONFLICTS (BDE)	98
WARM MIX ASPHALT (BDE)	103
WEEKLY DBE TRUCKING REPORTS (BDE)	107
WORKING DAYS (BDE)	107
BRACED EXCAVATION	108

BRACED EXCAVATION

Effective: August 9, 1995

Revised: May 18, 2011

Description. This work shall include the installation of a bracing system, excavation, and backfilling to the elevation of the existing grade according to Section 502 and the following. The bracing system shall be designed and installed to prevent the movement of soil, structures, pavements and/or utilities adjacent to the excavated area.

Construction Requirements. The bracing system shall support excavations by the use of sheeting, timber or plates. The Contractor shall submit design calculations and shop drawings prepared and sealed by an Illinois Licensed Structural Engineer for the bracing system. Shop drawings shall show all necessary details for the construction of the bracing system. The design calculations and shop drawings shall be submitted to the Engineer for review and approval.

This work shall not proceed without the approval and authorization of the Engineer. However, in any event, the Contractor shall be fully responsible for the safety, stability and adequacy of the bracing system and shall be solely responsible and liable for all damages resulting from his construction operations or from failure or inadequacy of the bracing system.

In the event the bracing system protecting the existing embankment fails or is otherwise inadequate, in the judgment of the Engineer, the Contractor shall, at his own expense, take all necessary steps to restore the embankments to a safe operating condition to the satisfaction of the Engineer.

Bracing members shall be installed as soon as an excavation level is reached to permit their installation. Bracing members shall be completely removed after the excavation is backfilled.

Method of Measurement. This work shall be measured in cubic yards (cubic meters) according to the requirements for structure excavation as specified in Section 502.12 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price per cubic yard (cubic meter) for BRACED EXCAVATION. Payment for BRACED EXCAVATION will be limited to those locations shown on the plans. All sheeting and bracing members associated with braced excavation will not be measured for payment but shall be included in the cost for BRACED EXCAVATION. No separate payment will be made for structure excavation where BRACED EXCAVATION is shown.

Added page 2-28-13