

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0040 RURAL
20400800	FURNISHED EXCAVATION	CU YD	53	53
25100630	EROSION CONTROL BLANKET	SO YD	50	50
44004250	PAVED SHOULDER REMOVAL	SO YD	22	22
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	22	22
50102400	CONCRETE REMOVAL	CU YD	38.2	38.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2563	2563
54003000	CONCRETE BOX CULVERTS	CU YD	38.2	38.2
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	56	56
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	36	36
* 63302400	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 5	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	176	176
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
X0322924	RETAINING WALL REMOVAL	SO FT	51	51
X2020502	BRACED EXCAVATION	CU YD	224	224
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	234	234
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	50	50

22

**Specialty Items*

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\woodshankr1\d0314887\	366C52-shr-details.dgn	DRAWN - RW	REVISED -			71	(113-RB)	FORD	9	3
#MODELNAME#	PLOT SCALE = 1/80.0000' / 1" in.	CHECKED -	REVISED -			CONTRACT NO. 66C52				
	PLOT DATE = 11/16/2012	DATE -	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA. TO STA.	[ILLINOIS] FED. AID PROJECT	