CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE 80% FED. 20% ST. ROADWAY 0001 URBAN
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	650	650
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	18,312	18,312
30201500	LIME	TON	366.3	366.3
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	199	199
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	4,025	4,025
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	3,271	3,271
35800100	PREPARATION OF BASE	SQ YD	305	305
35800200	AGGREGATE BASE REPAIR	TON	106	106
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	7,605	7,605
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,190	1,190
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	397	397
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	1.9	1.9
40300500	COVER COAT AGGREGATE	TON	7.7	7.7
40300600	SEAL COAT AGGREGATE	TON	3.9	3.9

15

* SPECIALTY ITEM

FILE NAME -	USER NAME -	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 407 (IL RTE 336) SUMMARY OF QUANTITIES
		DRAWN - TJD	REVISED -		
	PLOT SCALE - 2.0000 ' / IN.	CHECKED - AWM	REVISED -		
	PLOT DATE - 12/17/2012	DATE - 12-12-12	REVISED -		SCALE: N/A SHEET NO. 3 OF 15 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
407	(55-3)A	McDONOUGH	671	7

CONTRACT NO. 68A42

ILLINOIS FED. AID PROJECT