

EXPLORATION TRENCH, 52" DEPTH

LOCATION	EXPLORATION TRENCH, 52" DEPTH
	FOOT
IL 336	
STA 708+00 TO STA 717+00 RT	900
STA 760+00 TO STA 779+00 LT	1,900
STA 785+00 TO STA 795+00 RT	1,000
STA 795+00 TO STA 802+00 LT	700
STA 795+00 TO STA 802+00 RT	700
STA 808+00 TO STA 841+00 LT	3,300
STA 808+00 TO STA 841+00 RT	3,300
STA 842+00 TO STA 846+00 LT	400
STA 842+00 TO STA 846+00 RT	400
STA 846+00 TO STA 873+00 LT	2,700
STA 846+00 TO STA 873+00 RT	2,700
ALONG RAMP D	2,400
ALONG RAMP A	1,200
TOTAL	21,600

PERMANENT SEEDING SCHEDULE

LOCATION	SEEDING			NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	MULCH, METHOD 2
	CLASS 2A	CLASS 4A	CLASS 5A					
	ACRE							
FAP 407 (IL 336)								
STA 538+00 TO STA 552+00	0.88	0.85	0.85	155.7	155.7	155.7	0.88	1.62
STA 552+00 TO STA 566+00	1.75	6.87	6.87	775.8	775.8	775.8	1.75	5.69
STA 566+00 TO STA 580+00	1.79	16.17	16.17	1616.4	1616.4	1616.4	1.79	6.76
STA 580+00 TO STA 594+00	1.03	9.84	9.84	978.3	978.3	978.3	1.03	3.37
STA 594+00 TO STA 609+00	1.92	3.23	3.23	463.5	463.5	463.5	1.92	3.74
STA 609+00 TO STA 624+00	1.92	2.19	2.19	369.9	369.9	369.9	1.92	4.02
STA 624+00 TO STA 638+00	1.71	3.17	3.17	439.2	439.2	439.2	1.71	2.34
STA 638+00 TO STA 652+00	1.79	4.62	4.62	576.9	576.9	576.9	1.79	3.26
STA 652+00 TO STA 666+00	1.79	11.69	11.69	1213.2	1213.2	1213.2	1.79	2.76
STA 666+00 TO STA 680+00	1.79	10.57	10.57	1112.4	1112.4	1112.4	1.79	3.91
STA 680+00 TO STA 694+00	1.96	9.64	9.64	1044.0	1044.0	1044.0	1.96	7.81
STA 694+00 TO STA 708+00	1.99	5.23	5.23	649.8	649.8	649.8	1.99	3.78
STA 708+00 TO STA 723+00	1.95	1.89	1.89	345.6	345.6	345.6	1.95	3.72
STA 723+00 TO STA 738+00	1.71	3.48	3.48	467.1	467.1	467.1	1.71	3.19
STA 738+00 TO STA 753+00	1.96	5.68	5.68	687.6	687.6	687.6	1.96	3.36
STA 753+00 TO STA 768+00	1.96	5.94	5.94	711.0	711.0	711.0	1.96	3.95
STA 768+00 TO STA 783+00	2.17	4.38	4.38	589.5	589.5	589.5	2.17	3.17
STA 783+00 TO STA 798+00	1.96	2.67	2.67	416.7	416.7	416.7	1.96	4.67
STA 798+00 TO STA 812+00	1.57	2.24	2.24	342.9	342.9	342.9	1.57	3.81
STA 812+00 TO STA 826+00	1.83	3.37	3.37	468.0	468.0	468.0	1.83	4.46
STA 826+00 TO STA 840+00	1.83	2.04	2.04	348.3	348.3	348.3	1.83	2.44
STA 840+00 TO STA 855+00	1.83	2.92	2.92	427.5	427.5	427.5	1.83	4.75
STA 855+00 TO STA 870+00	1.96	2.21	2.21	375.3	375.3	375.3	1.96	4.17
STA 870+00 TO STA 885+00	1.96	2.24	2.24	378.0	378.0	378.0	1.96	4.20
STA 885+00 TO STA 897+00	1.45	2.29	2.29	336.6	336.6	336.6	1.45	2.93
RAMP L								
STA 60+50 TO STA 72+05	0.80	14.45	14.45	1372.5	1372.5	1372.5	0.80	11.98
RAMP K								
STA 101+50 TO STA 117+00	1.16	16.70	16.70	1607.4	1607.4	1607.4	1.16	14.79
CH 14 (1350N)								
STA 2005+50 TO STA 2008+81.7	0.27	0	0	24.3	24.3	24.3	0.27	0.27
STA 2009+80 TO STA 2022+75	1.08	0	0	97.2	97.2	97.2	1.08	0
EMORY RD (950E)								
STA 3013+00 TO STA 3021+00	3.21	0	0	288.9	288.9	288.9	3.21	1.67
CH 20 (1500N)								
STA 5000+00 TO STA 5010+00	3.03	0	0	272.7	272.7	272.7	3.03	1.49
STA 5010+00 TO STA 5025+00	6.30	0	0	567.0	567.0	567.0	6.30	0.00
STA 5025+00 TO STA 5031+00	1.68	0	0	151.2	151.2	151.2	1.68	1.68
STA 5042+00 TO STA 5050+00	1.45	0	0	130.5	130.5	130.5	1.45	1.45
1100E								
STA 6005+00 TO STA 6017+61.81	4.40	0	0	396.0	396.0	396.0	4.40	4.40
STA 6020+37.5 TO STA 6032+00	2.34	0	0	210.6	210.6	210.6	2.34	2.34
RAMP D								
STA 207+95 TO STA 219+05	0.46	4.47	4.47	443.7	443.7	443.7	0.46	4.66
RAMP A								
STA 322+40 TO STA 331+82	0.40	5.73	5.73	551.7	551.7	551.7	0.40	3.73
US 67								
STA 439+00 TO STA 454+00	0.98	0	0	88.2	88.2	88.2	0.98	0.32
SERVICE DRIVE								
STA 10838+00 TO STA 10855+00	2.28	0	0	205.2	205.2	205.2	2.28	2.28
STA 10855+00 TO STA 10870+45.6	2.94	0	0	264.6	264.6	264.6	2.94	2.24
TOTALS	77.24	166.77	166.77	21960.9	21960.9	21960.9	77.24	151.18
USE	77.25	167.00	167.00	21,961	21,961	21,961	77.25	151.25

HEAVY DUTY EROSION CONTROL BLANKET

STATION TO STATION	SIDE	HEAVY DUTY EROSION CONTROL BLANKET	
		SQ YD	
FAP 407 (IL 336)			
550+83	554+10	LT	2,115.6
555+16	559+00	LT	2,958.5
556+00	560+66	RT	3,427.0
562+96	568+35	LT	9,182.8
565+77	569+08	RT	4,863.4
571+00	584+31	LT	38,534.3
571+89	584+23	RT	27,736.3
586+00	592+00	LT	7,947.1
586+00	592+00	RT	8,495.2
606+45	609+52	LT	4,852.7
606+85	609+19	RT	2,401.9
632+00	636+00	LT	4,057.5
632+00	646+00	RT	16,157.9
649+00	662+00	LT	30,593.3
652+00	681+00	RT	70,000.0
675+00	680+00	LT	3,663.9
681+00	684+00	LT	7,395.6
684+23	686+00	RT	1,671.7
690+00	692+00	LT	2,268.8
690+00	692+00	RT	2,850.0
700+00	705+00	LT	8,481.7
700+00	707+00	RT	8,165.6
721+50	730+39	LT	4,899.6
734+00	743+00	LT	5,988.9
734+00	765+19	RT	39,218.5
776+00	780+00	RT	10,459.4
779+00	783+00	LT	5,884.0
818+50	821+50	RT	3,605.1
826+19	829+00	RT	6,924.7
887+18	895+00	LT	3,897.3
RAMP L			
57+00	66+00	RT	11,395.6
60+39	66+00	LT	4,413.2
RAMP K			
108+00	120+60	RT	11,035.1
112+00	115+50	LT	3,807.2
RAMP A			
321+85	333+50	RT	11,635.3
RAMP D			
215+50	219+25	RT	1,320.0
CH 14 (1350N)			
2009+33	2023+03	RT	5,704.7
2009+42	2022+75	LT	7,379.5
EMORY ROAD (950E)			
3013+00	3016+60	LT	6,997.2
3018+89	3019+21	LT	280.5
3018+94	3019+25	RT	180.8
CH 20 (1500N)			
5004+00	5008+70	RT	3,056.9
5004+00	5009+92	LT	4,384.1
5011+57	5021+00	RT	8,191.6
5013+00	5021+00	LT	6,805.0
US 67			
445+61	451+33	LT	3,196.6
SERVICE DRIVE			
10867+81	10870+95	LT	3,392.2
TOTAL			441,873.9
USE			441,874

NOTE: REFER TO EROSION CONTROL PLANS FOR LOCATIONS.

TEMPORARY EROSION CONTROL SEEDING

LOCATION	TEMPORARY EROSION CONTROL SEEDING	MOWING
	POUND	ACRES
IL 336		
STA 541+57.14 TO STA 552+0	191	1.91
STA 552+00 TO STA 566+00	332	3.32
STA 566+00 TO STA 580+00	332	3.32
STA 580+00 TO STA 594+00	350	3.50
STA 594+00 TO STA 609+00	354	3.54
STA 609+00 TO STA 624+00	354	3.54
STA 624+00 TO STA 638+00	316	3.16
STA 638+00 TO STA 652+00	332	3.32
STA 652+00 TO STA 666+00	332	3.32
STA 666+00 TO STA 680+00	332	3.32
STA 680+00 TO STA 694+00	294	2.94
STA 694+00 TO STA 708+00	314	3.14
STA 708+00 TO STA 723+00	368	3.68
STA 723+00 TO STA 738+00	255	2.55
STA 738+00 TO STA 753+00	368	3.68
STA 753+00 TO STA 768+00	368	3.68
STA 768+00 TO STA 783+00	354	3.54
STA 783+00 TO STA 798+00	368	3.68
STA 798+00 TO STA 812+00	295	2.95
STA 812+00 TO STA 826+00	344	3.44
STA 826+00 TO STA 840+00	344	3.44
STA 840+00 TO STA 855+00	344	3.44
STA 855+00 TO STA 870+00	368	3.68
STA 870+00 TO STA 885+00	368	3.68
STA 885+00 TO STA 895+00	246	2.46
RAMP L	191	1.91
RAMP K	246	2.46
RAMP A	154	1.54
RAMP D	165	1.65
CH 14 (1350N)	130	
EMORY RD (950E)	306	
CH 20 (1500N)	1,185	
1100E	645	
US 67	98	
SERVICE DRIVE	522	
TOTAL	11,865	89.79
USE	11,865	90