NOTE : SOME TREES ARE SHOWN FOR INDIVIDUAL REMOVAL THAT LIE IN AREAS WHERE TREE REMOVAL IS PAID FOR IN ACRES. THESE TREES SHALL NOT BE PAID FOR INDIVIDUALLY, BUT CONSIDERED INCLUDED IN TREE REMOVAL, ACRES. SEE SCHEDULE OF QUANTITIES FOR THOSE TREES PAID FOR INDIVIDUALLY AS UNITS.

SEC 27, T 6 N, R 3 W, 4th PM

JOHN E. & NANCY L. LAVERDIERE

PROPOSED TEMPORARY EASEMENT LINE

PROPOSED TEMPORARY EASEMENT LINE

PROPOSED R.O.W. LINE

℄ SURVEY & CONSTRUCTION
950E

LIMITS OF CONSTRUCTION

℄ SURVEY & CONSTRUCTION
FAP 407 (IL RTE 336)

MATCH LINE STATION 3013+00

3000+00 | 3005+00 | 950E (EMORY RD) | 3010+00

WESTERN ILLINOIS UNIVERSITY

℄ SURVEY & CONSTRUCTION
1400N (TOWER RD.)
(BY OTHERS)

PROPOSED R.O.W. LINE

PROPOSED TEMPORARY EASEMENT LINE

WESTERN ILLINOIS UNIVERSITY

50 0 50 100 150 200 250
SCALE IN FEET

LEGEND

- ⊠20" TREE REMOVAL
- TBR TO BE REMOVED
- TREE REMOVAL, ACRES
- PAVEMENT REMOVAL
- FENCE REMOVAL
- PAVEMENT PATCHING
- REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

PLAN — SURVEYED — PLOTTED — ALIGNMENT CHECKED — RT. OF WAY CHECKED — CADD FILE NAME — NOTE BOOK — NO. — BY — DATE

SEC 22, T 6 N, R 3 W, 4th PM

PROPOSED TEMPORARY EASEMENT LINE

BUILDING REMOVAL NO. 5

REMOVING EXISTING SEPTIC TANK - 1 EACH

BUILDING REMOVAL NO. 6

PROPOSED R.O.W. LINE

BARBARA HINMAN

GREGORY M. KERR

REMOVAL OF EXISTING STRUCTURES NO. 2 - 1 EACH

LIMITS OF PAVEMENT REMOVAL FOR PAVEMENT PATCHING

LIMITS OF CONSTRUCTION

℄ SURVEY & CONSTRUCTION
950E

SEALING ABANDONED WATER WELLS - 1 EACH BORED, 24" X 60'

MATCH LINE STATION 3013+00

950E (EMORY RD) | 3015+00 | 3020+00 | 3025+00

4' BARB WIRE FENCE

LIMITS OF CONSTRUCTION

PROPOSED R.O.W. LINE

BUILDING REMOVAL NO. 7

PROPOSED TEMPORARY EASEMENT LINE

BARBARA HINMAN

50 0 50 100 150 200 250
SCALE IN FEET

PROFILE — SURVEYED — PLOTTED — CROSS SECTIONS CHECKED — BAL. NOTED — STRUCTURE NOTATNS CHKD — NOTE BOOK — NO. — BY — DATE

FILE NAME = V:\Transportation\2891\Grading Plans\2891R21(950E).dgn	USER NAME = jdeen	DESIGNED - JRB	REVISED -
		DRAWN - RLR	REVISED -
	PLOT SCALE = 100.00 ' / IN.	CHECKED - AWM	REVISED -
	PLOT DATE = 12/12/2012	DATE - 12-12-12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 407 (IL RTE 336)
REMOVAL PLAN 950E – STATION 2998+00 TO STATION 3027+50

SCALE: 1"=50' | SHEET NO. 2 OF 8 SHEETS | STA. 2998+00 | TO STA. 3027+50

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
407	(55-3)A	McDONOUGH	671	93
		CONTRACT NO. 68A42		
	ILLINOIS FED. AID PROJECT			