

PIPE CULVERT REMOVAL	
LOCATION	FOOT
STA. 254+31 TO 254+65	33.6
STA. 261+04	3.5
TOTAL	38

METAL END SECTION 15"	
LOCATION	EACH
STA. 254+31	1
STA. 254+65	1
TOTAL	2

PIPE CULVERTS, CLASS D, TYPE 1 15"	
LOCATION	FOOT
STA. 254+31 TO 254+65	33.6
TOTAL	34

REINFORCEMENT BARS	
LOCATION	POUND
STA. 261+04	35
STA. 261+28	30
TOTAL	65

CONCRETE COLLAR	
LOCATION	CU YD
STA. 261+04	0.6
STA. 261+28	0.5
TOTAL	1.1

TRAFFIC CONTROL AND PROTECTION STANDARD 701201	
LOCATION	L. SUM
STA. 251+48 TO 278+60	1
TOTAL	1

PRECAST REINF. CONC. FLARED END SECTIONS 18"	
LOCATION	EACH
STA. 261+28	1
TOTAL	1

PIPE CULVERT, CLASS A, TYPE 1 18"	
LOCATION	FOOT
STA. 261+28	12
TOTAL	12

TRAFFIC CONTROL AND PROTECTION STANDARD 701326	
LOCATION	L. SUM
STA. 251+48 TO 278+60	1
TOTAL	1

PRECAST REINF. CONC. FLARED END SECTIONS 24"	
LOCATION	EACH
STA. 261+04	1
TOTAL	1

PIPE CULVERT, CLASS A, TYPE 1 EQUIV. ROUND-SIZE 24"	
LOCATION	FOOT
STA. 261+04	12
TOTAL	12

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL. DA.
STA. 251+48 TO 278+60	5
TOTAL	5

FILE NAME = D468A71-sht-plan.dgn

USER NAME = keithbr
 PLOT SCALE = 100.0000' / in.
 PLOT DATE = 12/12/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	(IIR)W-1	PEORIA	33	10
			CONTRACT NO. 68A71	
ILLINOIS FED. AID PROJECT				