

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY 0004 RURAL	ROADWAY 0005 RURAL	SAFETY 0021 RURAL
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,924	1608.4		315.6
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,796	447.5	296.1	3052.4
44004250	PAVED SHOULDER REMOVAL	SQ YD	706	533.8		172.2
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	496	201.9	107.6	186.5
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	300	63.7	124.6	111.7
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,501	1,005.2	85.6	2,410.2
48101200	AGGREGATE SHOULDERS, TYPE B	TON	859	143.3	397.1	318.6
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	583	381		202
50105220	PIPE CULVERT REMOVAL	FOOT	303	127.7		175.3
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	18			18
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	43	43		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	68		68	
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	51			51
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	50			50

FILE NAME *	USER NAME * cbrbrers	DESIGNED - JWC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\puidot\cbrbrers\08259638\0272E31-shs-sdq.dgn	DRAWN - JWC	REVISED -							(11N,TS-2RS-5&7B)RS-3	ADAMS	194	5
Default	PLOT SCALE * 3/32=000' / 1" dm	CHECKED - RSC	REVISED -		SCALE:	SHEET 3 OF 11 SHEETS	STA.	TO STA.	CONTRACT NO. 72E31			
	PLOT DATE * Jan-28-2013 8:13:03PM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							