

LOCATION	PATCHING SCHEDULE, CLASS A PATCHES				SAW CUTS			TIE BARS		PATCHING REINFORCEMENT						
	LENGTH (FOOT)		FOOT	SQ YD	(SQ YD)			(FOOT)		(EACH)		(SQ YD)				
	PASSING	DRIVING	WIDTH	FULL DEPTH	TY II	TY III	TY IV	TY II	TY III	TY IV	PASSING	DRIVING	PASSING	DRIVING		
ADAMS COUNTY																
13+02	12.00		12.00	16.0		16.0					72.0			16.0		
12+74	5.00		12.00	6.7	6.7						58.0			6.7		
12+44		8.00	12.00	10.7				10.7				64.0		10.7		
11+13		8.00	12.00	10.7				10.7				64.0		10.7		
11+01	15.00		12.00	20.0		20.0					78.0			20.0		
10+50		5.00	12.00	6.7				6.7				58.0		6.7		
8+48	48.00		12.00	64.0			64.0				144.0		25	64.0		
7+40	5.00		12.00	6.7	6.7						58.0			6.7		
7+07	8.00		12.00	10.7	10.7						64.0			10.7		
6+83		25.00	12.00	33.3					33.3			98.0	13	33.3		
6+83	25.00		12.00	33.3			33.3				98.0		13	33.3		
6+31	5.00		12.00	6.7	6.7						58.0			6.7		
6+15	10.00		12.00	13.3	13.3						68.0			13.3		
2+06		32.00	12.00	42.7					42.7			112.0	17	42.7		
1+74		5.00	12.00	6.7				6.7				58.0		6.7		
PIKE COUNTY																
1008+11	5.00		12.00	6.7	6.7						58.0			6.7		
1015+06	6.00		12.00	8.0	8.0						60.0			8.0		
1078+64		5.00	12.00	6.7				6.7				58.0		6.7		
1140+25		5.00	12.00	6.7				6.7				58.0		6.7		
1140+88		5.00	12.00	6.7				6.7				58.0		6.7		
1155+78		5.00	12.00	6.7				6.7				58.0		6.7		
1208+66		5.00	12.00	6.7				6.7				58.0		6.7		
1225+49		5.00	12.00	6.7				6.7				58.0		6.7		
1227+39		5.00	12.00	6.7				6.7				58.0		6.7		
1230+83		5.00	12.00	6.7				6.7				58.0		6.7		
1230+83	5.00		12.00	6.7	6.7						58.0			6.7		
1237+05	5.00		12.00	6.7	6.7						58.0			6.7		
1240+18		5.00	12.00	6.7				6.7				58.0		6.7		
1240+36		5.00	12.00	6.7				6.7				58.0		6.7		
1240+70		5.00	12.00	6.7				6.7				58.0		6.7		
1242+30		5.00	12.00	6.7				6.7				58.0		6.7		
1266+96		5.00	12.00	6.7				6.7				58.0		6.7		
1335+62		22.00	12.00	29.3					29.3			92.0	12	29.3		
1335+62	18.00		12.00	24.0		24.0					84.0			24.0		
1359+46		8.50	12.00	11.3				11.3				65.0		11.3		
1389+32		18.00	12.00	24.0					24.0			84.0		24.0		
1390+79		5.00	12.00	6.7				6.7				58.0		6.7		
1391+98		5.00	12.00	6.7	6.7			6.7				58.0		6.7		
23+10 **		5.00	16.00	8.9				8.9				58.0		8.9		
TOTALS				520.9	78.8	60.0	97.3	155.5	24.0	105.3	1016.0	1623.0	38	42	236.1	284.8

** ENTRANCE OF RAMP