

INDEX OF SHEETS

- 1 COVER
- 2 INDEX OF SHEETS, GENERAL NOTES, & LIST OF STANDARDS
- 3-3A SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5 TYPICAL CROSS SECTIONS
- 6-9 GENERAL PLANS
- 10 DETAIL SHEET
- 10A TRAFFIC CONTROL AND PROTECTION, SPECIAL
- 11-5B BRIDGE REPAIR PLANS

LIST OF STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701422-05 LANE CLOSURE, MULTILANE, FOR SPEEDS \geq 45 MPH TO 55 MPH
- 701901-02 TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE AND ROADWAY HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NORMAL CONSTRUCTION VARIATIONS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT BID FOR THE WORK.
4. IN ADDITION TO TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF THE BRIDGE DECK AND BRIDGE APPROACH PAVEMENT IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
5. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM ANY UNANTICIPATED UTILITY INTERFERENCE. FOR ADDITIONAL INFORMATION, CONTACT THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.) SYSTEM AT (800) 892-0123 OR 811.
6. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTOR TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERAL FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORK FORCE TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION RELATED SKILLS. E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSE WORK (CARPENTRY, CONCRETE FLAT WORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION. TO PREPARE THEM FOR A CAREER IN THEIR HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.
7. EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT. TO PREVENT THE SEALER FROM BEING APPLIED TO THE MARKINGS AND TO PROTECT THE REFLECTIVE PROPERTIES OF THE MARKINGS. THE TEMPORARY COVERING MATERIAL USED SHALL BE SUCH THAT IT WILL NOT AFFECT THE MARKING'S REFLECTIVITY WHEN REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR CONCRETE SEALER AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
8. CONTRACTOR MUST PROTECT ALL BRIDGE LIGHTING, UTILITIES, FIXTURES, CONDUITS, ETC. DURING WORK. ANY DAMAGE MUST BE REPORTED TO ENGINEER IMMEDIATELY.
9. CONTRACTOR SHALL FIELD VERIFY ALL DECK REPAIR LIMITS WITH ENGINEER PRIOR TO BEGINNING WORK.

COMMITMENTS

I. CONTRACTOR SHALL NOTIFY THE FOLLOWING INDIVIDUALS AT LEAST TWO WEEKS PRIOR TO PROCEEDING WITH THIS WORK:

MISSOURI DEPARTMENT OF TRANSPORTATION
1590 WOODLAKE DRIVE
CHESTERFIELD, MO 63017
MR. ED HASSINGER, P.E.
DISTRICT ENGINEER
314-275-1500

MADISON COUNTY TRANSIT DISTRICT
1 TRANSIT WAY PO BOX 7500
GRANITE CITY, IL 62010
MR. JERRY KANE
MANAGING DIRECTOR
618-797-4600

GREAT RIVERS GREENWAY
6174A DELMAR BOULEVARD
ST. LOUIS, MO 63112
MS. SUSAN TRAUTMAN
EXECUTIVE DIRECTOR
314-436-7009

LEAGUE OF ILLINOIS BICYCLISTS
2550 CHESHIRE DRIVE
AURORA, IL 60504
MR. ED BARSOTTI
EXECUTIVE DIRECTOR
630-978-0583

METRO EAST PARKS AND RECREATION DISTRICT
104 UNITED DRIVE
COLLINSVILLE, IL 62234
MR. MICHAEL BUEHLHORN
EXECUTIVE DIRECTOR
618-346-4905

TRAILNET
411 NORTH 10TH STREET SUITE 202
ST. LOUIS, MO 63101
MS. ANN RIVERS MACK
EXECUTIVE DIRECTOR
314-436-1324 EXT 105

FILE NAME	USER NAME * #USER*	DESIGNED - GEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, COMMITMENTS & LIST OF STANDARDS				F.A.P. RTE. 304	SECTION 1008-105-1	COUNTY MADISON	TOTAL SHEETS 58	SHEET NO. 2
#FILE#	PLOT SCALE * #SCALE*	DRAWN - LAC	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 76E73		
	PLOT DATE * #DATE*	CHECKED - MDP	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - 11/16/2012	REVISED -										