

SCHEDULE OF QUANTITIES FOR BRIDGE DECK CONCRETE SEALER

STA	TO	STA	LENGTH (FT)	AVG. WIDTH (FT)	DECK AREA TO BE SEALED (SQ FT)	OUTSIDE PARAPET TO BE SEALED (SF/LINEAR FT)	MEDIAN PARAPET TO BE SEALED (SF/LINEAR FT)	OUTSIDE PARAPET AREA TO BE SEALED (SQ FT)	MEDIAN PARAPET AREA TO BE SEALED (SQ FT)	AVERAGE MEDIAN WIDTH (FT)	MEDIAN TO BE SEALED (SQ FT)
208+35.00		224+43.04	1608.04	80	128643.2	3.84	3.03	12349.7	9744.7	1.5	2344.5
224+43.04		225+21.50	78.46	80	6276.8	3.84	3.03	602.6	475.5	2.0	159.4
225+21.50		227+22.00	200.50	80	16040.0	3.84	3.67	1539.8	1471.7	4.7	933.5
227+22.00		235+18.00	796.00	80	63680.0	3.84	3.67	6113.3	5842.6	8.0	6368.0
235+18.00		237+18.50	200.50	80	16040.0	3.84	3.67	1539.8	1471.7	4.7	933.1
237+18.50		237+97.12	78.62	80	6289.6	3.84	3.03	603.8	476.4	2.0	159.7
237+97.12		254+55.00	1657.88	80	132630.4	3.84	3.03	12732.5	10046.8	1.5	2417.2
SUBTOTAL BRIDGE DECK CONCRETE SEALER (SQ FT)					369600.0			35481.6	29529.4		13315.3
TOTAL BRIDGE DECK CONCRETE SEALER FOR BRIDGE DECK * (SQ FT)								447926			