



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 22, 2013

SUBJECT: FAU 5355 (Bethany Road)
Project M-5017(048)
Section 10-00167-01-WR (City of DeKalb)
DeKalb County
Contract No. 87544
Item 041
March 8, 2013 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Revised sheet 1 of the Plans.**
- 2. Revised page 1 of the Schedule of Prices.**
- 3. Revised page 1 of the Table of Contents.**
- 4. Revised page 1 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "AE" written to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
DEKALB	037	03	10-00167-01-WR(CITY OF DEKALB)	M-5017/048/000	FAU 5355

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
K1004595	PRUN SAFETY/EQUIP CLR	L SUM	1.000 X	=		=	
XX003032	GATE VALVES 12	EACH	3.000 X	=		=	
XX005472	DRAINAGE STRUCTURE SP	EACH	12.000 X	=		=	
XX007031	FRAME & GRATE SPECIAL	EACH	1.000 X	=		=	
XX008567	MAN TA 4 DIA	EACH	1.000 X	=		=	
XX008569	CB TA 4 DIA	EACH	2.000 X	=		=	
XX008730	DBL HANDHOLE ADJUST	EACH	1.000 X	=		=	
XX008815	TEMP PAVT PATCH 2	SQ YD	121.000 X	=		=	
X0326806	WASHOUT BASIN	L SUM	1.000 X	=		=	
X0327036	BIKE PATH REM	SQ YD	80.000 X	=		=	
X2130010	EXPLOR TRENCH SPL	FOOT	100.000 X	=		=	
X4401198	HMA SURF REM VAR DP	SQ YD	4,648.000 X	=		=	
X4430200	REF CR CONT TR SPL	FOOT	686.000 X	=		=	
X4811900	AGGREGATE SHLDS SPL	TON	136.000 X	=		=	
X5610662	WATER MAIN ABANDON 12	FOOT	374.000 X	=		=	

Revised 2/22/13

TABLE OF CONTENTS

<u>DESCRIPTION</u>	<u>PAGE</u>
LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS	2
REMOVAL OF EXCAVATED MATERIAL AND CLEAN CONSTRUCTION OR DEMOLITION DEBRIS	2
EARTH EXCAVATION.....	2
GENERAL MAINTENANCE AND MOWING OF TURF AREAS	3
TEMPORARY DITCH CHECKS	3
AGGREGATE SUBGRADE IMPROVEMENT - UNDERCUTS	3
AGGREGATE SHOULDERS (SPECIAL)	4
AGGREGATE WEDGE SHOULDER, TYPE B.....	4
SAW CUTTING	4
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.....	5
BIKE PATH REMOVAL.....	5
TEMPORARY PAVEMENT PATCH, 2 INCH	5
STRIP REFLECTIVE CRACK CONTROL TREATMENT.....	6
REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL	6
CATCH BASINS AND MANHOLES.....	7
DRAINAGE STRUCTURE SPECIAL.....	7
INLETS, SPECIAL	7
CHANGEABLE MESSAGE SIGN	8
EXPLORATION TRENCH, SPECIAL	8
PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE.....	9
WASHOUT BASIN	9
TEMPORARY INFORMATION SIGNING	10
TEMPORARY CONSTRUCTION FENCE	11
WATER MAIN	11

STATE OF ILLINOIS
SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction, Adopted January 1, 2012", the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the "Supplemental Specifications and Recurring Special Provisions" indicated on the Check Sheet included herein, which apply to and govern the construction of Route FAU 5355, Section 10-00167-01-WR, in DeKalb County, and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

Contract # 87544

LOCATION OF PROJECT

The project is located along the centerline of Bethany Road from North First Street to approximately 650 feet east of North First Street and from approximately 840 feet east of North First Street to approximately 25 feet west of Fairway Oaks/Meadow Trail West. The gross length of the improvement is 1673.8 feet (0.317 mile) and net length is 1481.1 feet (0.281 mile).

DESCRIPTION OF PROJECT

The work consists of pavement removal and reconstruction, placement of embankment, pavement milling and overlay, shoulder construction, traffic signal modifications, sidewalk and curb ramp constructions, multi-use path construction, placement of pavement marking, landscaping and all incidental and collateral work necessary to complete the project as shown on plans and as described herein.