

# SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						80% FEDERAL 20% STATE	
						ROADWAY 0003 URBAN	TRAINEES 0042 URBAN
		20101100	TREE TRUNK PROTECTION	EACH	4	4	
S		20200100	EARTH EXCAVATION	CU YD	1,910	1910	
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	600	600	
S		20400800	FURNISHED EXCAVATION	CU YD	775	775	
		20800150	TRENCH BACKFILL	CU YD	480	480	
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	2,900	2900	
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	5,271	5271	
		25000110	SEEDING, CLASS IA	ACRE	1.25	1.25	
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	113	113	
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	113	113	
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	113	113	
		25100630	EROSION CONTROL BLANKET	SO YD	5,801	5801	
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	550	550	
S		28000305	TEMPORARY DITCH CHECKS	FOOT	190	190	
		28000400	PERIMETER EROSION BARRIER	FOOT	2,273	2273	
		28000500	INLET AND PIPE PROTECTION	EACH	40	40	
S		30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	600	600	
S		30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	3,506	3506	
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	365	365	
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	1,133	1133	
		35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	365	365	
S		40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10	
		40600300	AGGREGATE (PRIME COAT)	TON	23	23	
		40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
		40600990	TEMPORARY RAMP	SO YD	201	201	
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,945	1945	
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	168	168	
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,047	1047	
		42001300	PROTECTIVE COAT	SO YD	629	629	
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	910	910	
		42400800	DETECTABLE WARNINGS	SO FT	203	203	
		44000100	PAVEMENT REMOVAL	SO YD	1,050	1050	

FILE NAME: \\P:\Programs\2012\120155\_Burke\Sub\3\CADD\Cv\11\Qm\Bh\A\S001.dgn

**WILLS BURKE KELSEY ASSOCIATES LTD.**  
110 West Main Street, Suite 201  
St. Charles, Illinois 60174

USER NAME = nparv18	DESIGNED -	REVISED -
PLOT SCALE = 1:1	DRAWN - NDP	REVISED -
PLT DATE = 12/20/2012	CHECKED - DPB	REVISED -
	DATE - 12/21/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 1	OF 5 SHEETS	STA. TO STA.

F.A.U. RTE. 5355	SECTION 10-00167-01-WR	COUNTY DEKALB	TOTAL SHEETS 78	SHEET NO. 4
CONTRACT NO. 87544				ILLINOIS FED. AID PROJECT