

SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						80% FEDERAL 20% STATE	
						ROADWAY 0003 URBAN	TRAINEES 0042 URBAN
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	435	435	
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	290	290	
		44000600	SIDEWALK REMOVAL	SQ FT	340	340	
		44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	24	24	
		44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	160	160	
S		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5,130	5130	
S		48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	40	40	
		50105220	PIPE CULVERT REMOVAL	FOOT	92	92	
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	810	810	
		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	251	251	
		550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	90	90	
		55100900	STORM SEWER REMOVAL 18"	FOOT	7	7	
		60238800	INLETS, TYPE A	EACH	2	2	
S		60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
		60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2	
		60402210	GRATES, TYPE B	EACH	2	2	
		60404800	FRAMES AND GRATES, TYPE 11	EACH	16	16	
		60404910	FRAMES AND GRATES, TYPE 20	EACH	1	1	
		60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2	
		60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	
		60500040	REMOVING MANHOLES	EACH	1	1	
		60500050	REMOVING CATCH BASINS	EACH	1	1	
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,376	2376	
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	186	186	
S		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
		67100100	MOBILIZATION	L SUM	1	1	
S		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
S		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
S		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14	
S		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,200	2200	

FILE NAME = \\P:\projects\2012\12185 Bethany\5355\Civil\Drawings\SummarySheet.dwg

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nparr13	DESIGNED -	REVISED -
PLOT SCALE = 1:1	DRAWN - NDP	REVISED -
PLOT DATE = 12/20/2012	CHECKED - DPB	REVISED -
	DATE - 12/21/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.U. RTE. 5355	SECTION 10-00167-01-WR	COUNTY DEKALB	TOTAL SHEETS 78	SHEET NO. 5
CONTRACT NO. B7544				
ILLINOIS FED. AID PROJECT				