

# SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						80% FEDERAL 20% STATE	
						ROADWAY 0003 URBAN	TRAINEES 0042 URBAN
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	64	64	
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,600	11600	
		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	800	800	
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	40	40	
		70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	936	936	
S		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,544	4544	
	•	72000100	SIGN PANEL - TYPE 1	SQ FT	52	52	
	•	72000200	SIGN PANEL - TYPE 2	SQ FT	10	10	
	•	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	8	
	•	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	102	102	
	•	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	336	336	
	•	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,718	6718	
	•	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	319	319	
	•	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,716	1716	
	•	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	610	610	
	•	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175	
S	*	78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	893	893	
S	*	78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	36	36	
S		78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,645	2645	
S	•	81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	353	353	
S	•	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2	2	
S	•	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
	•	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	100	100	
	•	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	100	100	
	•	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	290	290	
	•	87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	814	814	
	•	87900200	DRILL EXISTING HANDHOLE	EACH	1	1	
	•	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1	
	•	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1	1	
	•	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	4	
	•	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	1	1	
S	•	88500100	INDUCTIVE LOOP DETECTOR	EACH	1	1	

FILE NAME = M:\Projects\2012\120185 BethanySgs\CADD\Civil\Open\Sheet\8003.dgn

**WILLS BURKE KELSEY ASSOCIATES LTD.**  
116 West Main Street, Suite 201  
St. Charles, Illinois 60174

USER NAME = nparris	DESIGNED -	REVISED -
PLOT SCALE = 1:1	DRAWN - NDP	REVISED -
PLOT DATE = 12/28/2012	CHECKED - DPB	REVISED -
	DATE - 12/21/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.U. RTE. 5355	SECTION 10-00167-01-WR	COUNTY DEKALB	TOTAL SHEETS 78	SHEET NO. 6
CONTRACT NO. 87544				
ILLINOIS FED. AID PROJECT				