

SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						80% FEDERAL 20% STATE	
						ROADWAY 0003 URBAN	TRAINEES 0042 URBAN
S	•	88600100	DETECTOR LOOP, TYPE I	FOOT	489	489	
	•	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	4	
S	•	89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	
S	•	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
S	•	89502380	REMOVE EXISTING HANDHOLE	EACH	2	2	
S		K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1	1	
S		X0326806	WASHOUT BASIN	L SUM	1	1	
S		X0327036	BIKE PATH REMOVAL	SO YD	80	80	
S		X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100	
S		X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	4,648	4648	
S		X4430200	REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL	FOOT	686	686	
S		X4811900	AGGREGATE SHOULDERS (SPECIAL)	TON	136	136	
S	•	X5610662	WATER MAIN TO BE ABANDONED, 12"	FOOT	374	374	
S	•	X5610712	WATER MAIN REMOVAL, 12"	FOOT	45	45	
S	•	X5611112	DUCTILE IRON WATER MAIN, CLASS 52 WITH POLYETHYLENE ENCASEMENT, 12"	FOOT	442	442	
S		X5619210	WATER VALVES TO BE ADJUSTED, SPECIAL	EACH	3	3	
S	•	X5620035	WATER SERVICE CONNECTION 1 1/2"	EACH	1	1	
S		X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	100	100	
S		X6024240	INLETS, SPECIAL	EACH	6	6	
S		X6026622	VALVE VAULTS TO BE REMOVED	EACH	2	2	
S		X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1	
S		X8140115	HANDHOLE TO BE ADJUSTED	EACH	1	1	
S	•	XX003032	GATE VALVES, 12"	EACH	3	3	
S		XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	12	12	
S		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
S		Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	28	28	
S		Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	569	569	
S		Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	12	12	
S		Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	362	362	
S		Z0076600	TRAINEES	HOUR	500		500
S		Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500		500
S		XX008815	TEMPORARY PAVEMENT PATCH, 2 INCH	SO YD	121	121	
S		XX008569	CATCH BASINS, TYPE A, 4'-DIAMETER	EACH	2	2	

FILE NAME = \\A:\Projects\2012\128185 - Burchingergs\00101 - Civil\Drawn\Drawn\Summary.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
116 West Main Street, Suite 201
St. Charles, Illinois 60174

USER NAME = nparis	DESIGNED -	REVISED -
PLOT SCALE = 1:1	DRAWN - NDP	REVISED -
PLOT DATE = 12/20/2012	CHECKED - DPB	REVISED -
	DATE - 12/21/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	10-00167-01-WR	DEKALB	78	7
CONTRACT NO. 87544				
ILLINOIS FED. AID PROJECT				