

SCHEDULE OF LANDSCAPING AND EROSION CONTROL QUANTITIES

LOCATION	OFF.	20101100	21101625	25000110	25000400	25000500	2500600	25100630	28000250	28000305	28000400	28000500
		TREE TRUNK PROTECTION	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 1A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING (5 APPS.)	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
		(EACH)	(SQ YD)	(SQ YD)	(LBS)	(LBS)	(LBS)	(SQ YD)	(LBS)	(FOOT)	(FOOT)	(EACH)
MAINLINE												
9+00 - 10+50	LT/RT		143.9	143.9	2.7	2.7	2.7	143.9	14.9		114.7	1
10+50 - 11+00	LT/RT		145.7	145.7	2.7	2.7	2.7	145.7	15.1		104.6	2
11+00 - 11+50	LT/RT		161.1	161.1	3.0	3.0	3.0	161.1	16.6		100.1	3
11+50 - 12+00	LT/RT		162.9	162.9	3.0	3.0	3.0	162.9	16.8		100.0	
12+00 - 12+50	LT/RT		162.9	162.9	3.0	3.0	3.0	162.9	16.8		100.0	2
12+50 - 13+00	LT/RT		162.9	162.9	3.0	3.0	3.0	162.9	16.8	20	100.0	
13+00 - 13+50	LT/RT		166.9	166.9	3.1	3.1	3.1	166.9	17.2		100.0	1
13+50 - 14+00	LT/RT		109.1	109.1	2.0	2.0	2.0	109.1	11.3		58.4	3
14+00 - 14+50	LT/RT		168.7	168.7	3.1	3.1	3.1	168.7	17.4	10	100.0	
14+50 - 15+00	LT/RT		179.7	179.7	3.3	3.3	3.3	179.7	18.6		100.0	2
15+00 - 15+50	LT/RT		120.1	120.1	2.2	2.2	2.2	120.1	12.4		79.9	1
15+50 - 16+00	LT/RT		166.2	166.2	3.1	3.1	3.1	166.2	17.2	20	100.0	3
16+00 - 16+50	LT/RT		21.0	21.0	0.4	0.4	0.4	21.0	2.2		34.8	4
16+50 - 17+00	LT/RT											
18+50 - 19+00	LT/RT											
19+00 - 19+50	LT/RT											
19+50 - 20+00	LT/RT		110.1	110.1	2.0	2.0	2.0	110.1	11.4		54.5	3
20+00 - 20+50	LT/RT		228.5	228.5	4.2	4.2	4.2	228.5	23.6	20	51.7	1
20+50 - 21+00	LT/RT		228.5	228.5	4.2	4.2	4.2	228.5	23.6		51.7	1
21+00 - 21+50	LT/RT		228.5	228.5	4.2	4.2	4.2	228.5	23.6	20	51.7	3
21+50 - 22+00	LT/RT		188.7	188.7	3.5	3.5	3.5	188.7	19.5		51.7	
22+00 - 22+50	LT/RT	1	180.0	180.0	3.3	3.3	3.3	180.0	18.6	10	51.7	
22+50 - 23+00	LT/RT	1	227.7	227.7	4.2	4.2	4.2	227.7	23.5		51.7	2
23+00 - 23+50	LT/RT		228.6	228.6	4.3	4.3	4.3	228.6	23.6	20	51.7	
23+50 - 24+00	LT/RT		199.4	199.4	3.7	3.7	3.7	199.4	20.6		37.6	
24+00 - 24+50	LT/RT		205.2	205.2	3.8	3.8	3.8	205.2	21.2	10	40.9	3
24+50 - 25+00	LT/RT		228.6	228.6	4.3	4.3	4.3	228.6	23.6	20	51.7	
25+00 - 25+50	LT/RT		228.6	228.6	4.3	4.3	4.3	228.6	23.6		51.7	1
25+50 - 26+00	LT/RT		228.6	228.6	4.3	4.3	4.3	228.6	23.6		51.7	
26+00 - 26+50	LT/RT		228.8	228.8	4.3	4.3	4.3	228.8	23.6	20	51.4	
26+50 - 27+00	LT/RT		229.7	229.7	4.3	4.3	4.3	229.7	23.7		50.0	2
27+00 - 27+50	LT/RT		107.2	107.2	2.0	2.0	2.0	107.2	11.1		50.0	
27+50 - 28+00	LT/RT		91.6	91.6	1.7	1.7	1.7	91.6	9.5		50.0	
28+00 - 28+50	LT/RT		31.6	31.6	0.6	0.6	0.6	31.6	3.3		18.7	2
MAINTENANCE / REPL.		2						530.0		20	210.0	
TOTAL		4	5,271.0	5,271.0	98.0	98.0	98.0	5,801.0	545.0	190	2,273	40
				1.25 AC	113 LBS	113 LBS	113 LBS		550 LBS			

FILE NAME: \\MINPro\jstest\2012\120125 - Bedden\3-CADD\3-CADD\3-CADD\3-CADD\3-CADD\Sch\SCHEDULE.dgn

WILLS BURKE KELSEY ASSOCIATES LTD
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nparrts	DESIGNED - XMA	REVISED -
PLT SCALE = 1:1	DRAWN - KMA	REVISED -
PLT DATE = 12/20/2012	CHECKED - DPB	REVISED -
	DATE - 12/21/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 1	OF 6 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	10-00167-01-WR	DEKALB	78	9
CONTRACT NO. 87544				
ILLINOIS FED. AID PROJECT				