

SCHEDULE OF PAVEMENT REMOVAL QUANTITIES

LOCATION	OFF.	40600990	44000100	X4401198	44000200	44000500	44000600	44201777	44201781	44300200	X0327036	X4430200
		TEMPORARY RAMP	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, VAR. DEPTH	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CLASS D PATCHES, TYPE II, 11 INCH	CLASS D PATCHES, TYPE III, 11 INCH	STRIP REFLECTIVE CRACK CONTROL TREATMENT (1)	BIKE PATH REMOVAL	REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL (2)
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)	(FOOT)	(SQ YD)	(FOOT)
MAINLINE												
9+00 - 10+50	LT/RT	92.0	35.6	282.0		68.1	27.0			161.0	79.9	
10+50 - 11+00	LT/RT		53.6	337.3		117.7	313.0			268.8		
11+00 - 11+50	LT/RT		75.1	243.3		42.9			24.4	250.5		88.0
11+50 - 12+00	LT/RT		77.8	198.1						254.6		
12+00 - 12+50	LT/RT		79.6	194.2					19.4	250.0		70.0
12+50 - 13+00	LT/RT		84.5	193.3						250.0		
13+00 - 13+50	LT/RT		87.2	192.2					38.4	250.0		140.0
13+50 - 14+00	LT/RT		89.1	190.4					19.0	250.0		70.0
14+00 - 14+50	LT/RT		35.9	187.0						250.0		
14+50 - 15+00	LT/RT		12.3	180.7					18.2	150.0		65.0
15+00 - 15+50	LT/RT		11.2	170.4						150.7		
15+50 - 16+00	LT/RT		18.4	253.4		20.5				180.4		
16+00 - 16+50	LT/RT			293.3						50.0		
16+50 - 17+00	LT/RT	39.0		214.5						37.2		
18+50 - 19+00	LT/RT	39.0		114.3						20.1		
19+00 - 19+50	LT/RT			272.2						50.0		
19+50 - 20+00	LT/RT			258.9		20.0				50.0		
20+00 - 20+50	LT/RT		9.9	140.5						197.8		
20+50 - 21+00	LT/RT		11.1	14.9						200.4		
21+00 - 21+50	LT/RT		11.1							200.4		44.0
21+50 - 22+00	LT/RT		11.1							180.2		
22+00 - 22+50	LT/RT		12.0					12.7		150.1		44.0
22+50 - 23+00	LT/RT		12.1					11.0		150.1		44.0
23+00 - 23+50	LT/RT		14.3							150.0		
23+50 - 24+00	LT/RT		18.5	11.2						149.9		
24+00 - 24+50	LT/RT		25.3	29.8						149.9		53.0
24+50 - 25+00	LT/RT		35.6	54.2						149.8		
25+00 - 25+50	LT/RT		54.0	87.3						149.8		
25+50 - 26+00	LT/RT		73.0	141.4						149.8		
26+00 - 26+50	LT/RT		55.2	186.9						152.5		
26+50 - 27+00	LT/RT	31.0	46.5	206.0		20.0			18.9	126.0		68.0
27+00 - 27+50	LT/RT											
27+50 - 28+00	LT/RT											
28+00 - 28+50	LT/RT											
ENTRANCES												
13+81	CE RT					90.6						
15+25	PE LT					111.7						
21+98	PE LT					125.1						
23+98	CE RT					107.0						
TOTAL		201.0	1050.0	4648.0	435.0	290.0	340.0	24.0	160.0	5130.0	80.0	686.0

(1) CRACK CONTROL FOR LOGINTUDINAL TREATMENTS (SYSTEM A)
 (2) CRACK CONTROL FOR TRANSVERSE TREATMENTS

FILE NAME = W:\Projects\2012\20120150_Bashony\523\CA001\Civil\09n\Sh\A\SCHEDULE12.dgn



USER NAME = mpraris	DESIGNED - KMA	REVISED -
DRAWN - KMA	CHECKED - DPB	REVISED -
PLOT SCALE = 1:1	DATE - 12/21/12	REVISED -
PLOT DATE = 12/28/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	10-00167-01-WR	DEKALB	78	10
CONTRACT NO. 87544				
ILLINOIS FED. AID PROJECT				