

SCHEDULE OF STRIPING AND SIGNING QUANTITIES

LOCATION	72000100	72000200	72400100	72800100	78000100	78000200	78000400	78000500	78000600	78000650	78009004	78009012	78300100
	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	REMOVE SIGN PANEL ASSEMBLY - TYPE A	TELESCOPING SIGN SUPPORT	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	PAVEMENT MARKING REMOVAL
	(SQ FT)	(SQ FT)	(EACH)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
MAINLINE													
9+00 - 10+50	7.50								226				229
10+50 - 11+00	3.75							47	204	38			
11+00 - 11+50					32	113	148	100					
11+50 - 12+00			1		113	113		100					
12+00 - 12+50	7.50			17	32	113		100					
12+50 - 13+00			1		113	113		100					
13+00 - 13+50					113	113		100					
13+50 - 14+00		10.00	1	34	80	160		65	1	29			
14+00 - 14+50			1		213	213		25	6				
14+50 - 15+00	27.00		2	34	213	213		25	12				
15+00 - 15+50					213	213		25	8				
15+50 - 16+00					218	218		13	21				
16+00 - 16+50					225	225			19				
16+50 - 17+00					116	116			10	109	8		38
17+00 - 17+50									13	225	13		145
17+50 - 18+00									10	225	9		124
18+00 - 18+50									4	225	3		124
18+50 - 19+00						109			1	109	3		72
19+00 - 19+50						125							
19+50 - 20+00						125							
20+00 - 20+50						125							
20+50 - 21+00			1			125							
21+00 - 21+50						125							
21+50 - 22+00						125							
22+00 - 22+50						125							
22+50 - 23+00						125							
23+00 - 23+50						125							
23+50 - 24+00						125							
24+00 - 24+50						125				12			
24+50 - 25+00						125							
25+00 - 25+50						125							
25+50 - 26+00						125							
26+00 - 26+50						125							
26+50 - 27+00						125							
27+00 - 27+50						125							
27+50 - 28+00						125							
28+00 - 28+50						45							
N. FIRST ST.													
100+00 - 100+50						100		13					42
100+50 - 101+00						200		25	28				111
101+00 - 101+50						200		25	8				91
101+50 - 102+00						200		25	4				87
102+00 - 102+50					32	150		63	2				126
102+50 - 103+00						100		100					100
103+00 - 103+50					32	100		100					132
103+50 - 104+00						100		100					100
104+00 - 104+50					32	82		94		48			218
104+50 - 105+00													
105+00 - 105+50													
105+50 - 106+00					16	42		74		48			175
106+00 - 106+50					32	100		100					132
106+50 - 107+00					16	100		100					116
107+00 - 107+50					32	100		100					132
107+50 - 108+00						200		27	7				92
108+00 - 108+50						200		25	11				94
108+50 - 109+00						200		25	15				98
109+00 - 109+50						160		20					67
ENTRANCES													
13+81 CE													
15+25 PE													
21+98 PE													
23+98 CE	6.25		1	17									
TOTAL	52	10	8	102	336	6,718	319	1,716	610	175	893	36	2,645

SCHEDULE OF TEMPORARY STRIPING QUANTITIES

LOCATION	70300100	70300210	70300220	70300250	70300280	70301000
	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL
	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
STAGE 1						
7+00 - 13+00			941	378	40	646
13+00 - 19+00			977	63	0	368
19+00 - 25+00			1,803	0	0	801
25+00 - 28+00			601	0	0	200
STAGE 2						
7+00 - 13+00			1,251	228	0	569
13+00 - 19+00			2,256	63	0	794
19+00 - 25+00			2,352	0	0	784
25+00 - 28+00			917	0	0	306
STAGE 3						
7+00 - 28+00	2,200	64				64
Maintenance			502	68		212
TOTAL	2,200	64	11,600	800	40	4,544

FILE NAME = W:\Projects\2012\1208155_Bachon\Sigs\CADD\Civil\Ogry\SHA\SCHEDULE.F5.dgn