

| SUMMARY OF QUANTITIES |  |        |                | CONSTRUCTION CODE |                       |
|-----------------------|--|--------|----------------|-------------------|-----------------------|
| CODE NO.              | ITEM   | UNIT   | TOTAL QUANTITY | ROADWAY           | BRIDGE                |
|                       |  |        |                | 0004<br>URBAN     | 0011<br>S.N. 048-6063 |
| 550A0640              | STORM SEWERS, CLASS A, TYPE 3 12"                              | FOOT   | 71             | 71                |                       |
| 550A0680              | STORM SEWERS, CLASS A, TYPE 3 18"                              | FOOT   | 128            | 128               |                       |
| 59100100              | GEOCOMPOSITE WALL DRAIN  | SQ YD  | 64             |                   | 64                    |
| 60218400              | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID        | EACH   | 2              | 2                 |                       |
| 60236200              | INLETS, TYPE A, TYPE 8 GRATE                                   | EACH   | 1              | 1                 |                       |
| 60600095              | CLASS SI CONCRETE (OUTLET)                                     | CU YD  | 0.6            | 0.6               |                       |
| 60603800              | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12              | FOOT   | 1027           | 1027              |                       |
| 60626500              | TRANSITIONAL COMBINATION CONCRETE CURB AND GUTTER              | FOOT   | 20             | 20                |                       |
| △ 63100085            | TRAFFIC BARRIER TERMINAL, TYPE 6                               | EACH   | 3              | 3                 |                       |
| △ 63100167            | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT             | EACH   | 3              | 3                 |                       |
| 63200310              | GUARDRAIL REMOVAL  | FOOT   | 504            | 504               |                       |
| 67000500              | ENGINEER'S FIELD OFFICE, TYPE B                                | CAL MO | 9              | 9                 |                       |
| 67100100              | MOBILIZATION   | L SUM  | 1              | 1                 |                       |
| 70400100              | TEMPORARY CONCRETE BARRIER                                     | FOOT   | 750            | 750               |                       |
| 70600240              | IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2 | EACH   | 2              | 2                 |                       |
| △ 78009004            | MODIFIED URETHANE PAVEMENT MARKING - LINE 4"                   | FOOT   | 1480           | 1480              |                       |
| △ 78100100            | RAISED REFLECTIVE PAVEMENT MARKER                              | EACH   | 7              | 7                 |                       |
| △ 78100105            | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)                     | EACH   | 3              | 3                 |                       |
| △ 80400100            | ELECTRIC SERVICE INSTALLATION                                  | EACH   | 1              | 1                 |                       |
| △ 81028350            | UNDERGROUND CONDUIT, PVC, 2" DIA.                              | FOOT   | 527            | 527               |                       |
| △ 81200230            | CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC                    | FOOT   | 348            | 348               |                       |
| △ 81400730            | HANDHOLE, COMPOSITE CONCRETE                                   | EACH   | 2              | 2                 |                       |
| △ 81702120            | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/2 NO. 8       | FOOT   | 5180           | 5180              |                       |
| △ 82500350            | LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP             | EACH   | 1              | 1                 |                       |
| △ 83006400            | LIGHT POLE, ALUMINUM, 30 FT. M.H., 10 FT. MAST ARM             | EACH   | 2              | 2                 |                       |
| △ 83600200            | LIGHT POLE FOUNDATION, 24" DIAMETER                            | FOOT   | 12             | 12                |                       |
| △ 87800215            | CONCRETE FOUNDATION, TYPE D                                    | EACH   | 1              | 1                 |                       |
| △ <del>XXXXXX</del>   | ROADWAY LUMINAIRE (SPECIAL)                                    | EACH   | 2              | 2                 |                       |
| △ <del>XXXXXX</del>   | DECORATIVE LUMINAIRE (SPECIAL)                                 | EACH   | 6              | 6                 |                       |
| △ <del>XXXXXX</del>   | DECORATIVE LIGHT POLE (SPECIAL)                                | EACH   | 6              | 6                 |                       |

| SUMMARY OF QUANTITIES |  |       |                | CONSTRUCTION CODE |                       |
|-----------------------|--|-------|----------------|-------------------|-----------------------|
| CODE NO.              | ITEM   | UNIT  | TOTAL QUANTITY | ROADWAY           | BRIDGE                |
|                       |  |       |                | 0004<br>URBAN     | 0011<br>S.N. 048-6063 |
| △ D2003776            | EVERGREEN, THUJA OCCIDENTALIS SMARAGD (EMERALD GREEN AMERICAN ARBORVITAE), 5' HEIGHT, BALLED AND BURLAPPED | EACH  | 34             | 34                |                       |
| △ X0325402            | MODIFY SPRINKLER SYSTEM  | L SUM | 1              | 1                 |                       |
| X2800520              | ABOVE GRADE INLET FILTERS  | EACH  | 6              | 6                 |                       |
| △ X5091730            | BRIDGE FENCE RAILING (SPECIAL)   | FOOT  | 308            |                   | 308                   |
| X5860110              | GRANULAR BACKFILL FOR STRUCTURES   | CU YD | 98             |                   | 98                    |
| X6020065              | INLETS, TYPE G-1, DOUBLE (SPECIAL)   | EACH  | 3              | 3                 |                       |
| X6021824              | INLET-MANHOLE, TYPE G-1, 4' DIAMETER, SPECIAL  | EACH  | 1              | 1                 |                       |
| X6060097              | CLASS SI CONCRETE (OUTLET), SPECIAL  | CU YD | 0.9            | 0.9               |                       |
| △ X8310214            | TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)   | EACH  | 1              | 1                 |                       |
| △ X6330725            | STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)  | FOOT  | 25             | 25                |                       |
| X7010216              | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)  | L SUM | 1              | 1                 |                       |
| △ X7016500            | TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)   | EACH  | 1              | 1                 |                       |
| X7240300              | SIGN REMOVAL   | EACH  | 4              | 4                 |                       |
| X7240500              | RELOCATE EXISTING SIGNS  | EACH  | 2              | 2                 |                       |
| Z0013798              | CONSTRUCTION LAYOUT  | L SUM | 1              | 1                 |                       |
| Z0026407              | TEMPORARY SHEET PILING   | SQ FT | 444            |                   | 444                   |
| Z0028462              | GEOTEXTILE RETAINING WALL  | SQ FT | 189            | 189               |                       |
| Z0043750              | PRECAST MODULAR BLOCK WALL   | SQ FT | 120            | 120               |                       |
| Z0046304              | PIPE UNDERDRAINS FOR STRUCTURES 4"   | FOOT  | 147            |                   | 147                   |
| Z0048865              | RAILROAD PROTECTIVE LIABILITY INSURANCE  | L SUM | 1              | 1                 |                       |
| Z0065704              | BITUMINOUS COATED AGGREGATE SLOPEWALL 6"   | SQ YD | 458            |                   | 458                   |

△ SPECIALTY ITEMS