

SUMMARY OF QUANTITIES

SP	PAY CODE	ITEM	UNITS	80% I/TEP 20% LOCAL QUANTITY	NON-I/TEP 100% LOCAL QUANTITY	TOTAL QUANTITY
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	122		122
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	256		256
	20101200	TREE ROOT PRUNING	EACH	18		18
	20400800	FURNISHED EXCAVATION	CU YD	120		120
	21101665	TOPSOIL FURNISH AND PLACE, 18"	SQ YD		289	289
*	25000100	SEEDING, CLASS 1	ACRE	1.5		1.5
	25100115	MULCH, METHOD 2	ACRE	1.5		1.5
	28000500	INLET AND PIPE PROTECTION	EACH	46		46
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1952		1952
*	35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	377		377
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	77		77
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		248	248
	40600990	TEMPORARY RAMP	SQ YD	668		668
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON		209	209
*	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1280		1280
*	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	68792		68792
*	42400800	DETECTABLE WARNINGS	SQ FT	1178		1178
*	44000100	PAVEMENT REMOVAL	SQ YD	2955	500	3455
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	962		962
	44000300	CURB REMOVAL	FOOT	3254		3254
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	146		146
*	44000600	SIDEWALK REMOVAL	SQ FT	39651		39651
	50801760	PIPE HANDRAIL	FOOT	28		28
	550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	798		798
*	56109210	WATER VALVES TO BE ADJUSTED	EACH	23		23
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		3
	60236700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	40		40
	60255500	MANHOLES TO BE ADJUSTED	EACH	2		2
	60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	6		6
	60500060	REMOVING INLETS	EACH	31		31
*	60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EX PAV)	FOOT	600	1143	1743
*	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EX PAV.)	FOOT	3815		3815
	87100100	MOBILIZATION	L SUM	1		1

* DENOTES SPECIAL PROVISION

SUMMARY OF QUANTITIES

SP	PAY CODE	ITEM	UNITS	80% I/TEP 20% LOCAL QUANTITY	NON-I/TEP 100% LOCAL QUANTITY	TOTAL QUANTITY
	72000100	SIGN PANEL - TYPE 1	SQ FT	8.0		8
Δ	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	360		360
Δ	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1264	341	1605
Δ	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1233	44	1277
Δ	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	192		192
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	496	142	638
Δ	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	20		20
Δ	* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT		951	951
Δ	* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT		92	92
Δ	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	185		185
Δ	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	310		310
Δ	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1
Δ	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4
Δ	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15		15
Δ	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6		6
Δ	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1
Δ	* 89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	2		2
Δ	89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1		1
Δ	* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1
Δ	* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2		2
*	X0322983	STONE CURB	FOOT	63		63
*	X0326522	PRECAST MODULAR RETAINING WALL	FOOT	272		272
*	X2020105	GRADING AND SHAPING BIKEWAY	UNIT	77		77
*	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD		2480	2480
*	X5510100	STORM SEWER REMOVAL	FOOT	372		372
*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
*	XX000300	CONCRETE STEPS	SQ FT	47		47
*	XX005283	BRICK PAVER CROSSWALK	SQ FT	2036		2036
*	XZ127900	RETAINING WALL REMOVAL	FOOT	266		266
*	Z0001110	GAS VALVE TO BE ADJUSTED	EACH	6		6
*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
*	Z0022800	FENCE REMOVAL	FOOT	393		393

* DENOTES SPECIAL PROVISION

Δ SPECIALTY ITEMS

PRINTED DATE: 1/17/2012
 C:\Users\ESL\Documents\Lincoln Park Shared Use Path\Drawings\Summary of Quantities.dwg

NO.	DATE	DESCRIPTION OF REVISIONS	NO.	DATE	DESCRIPTION OF REVISIONS