

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
656	06-00265-00-BR	SHELBY	29	7

NEOGA BRIDGE PROJECT

CONTRACT # 95701

EXPLORATORY TRENCH - 72" DEPTH

EXPLORATORY TRENCH SHALL BE PLACED AT LOCATIONS AS DIRECTED BY THE ENGINEER.

THE QUANTITY IN THE PLANS IS ESTIMATED TO ESTABLISH A CONTRACT UNIT PRICE. FINAL PAYMENT WILL BE MADE BASED UPON THE AMOUNT ORDERED AND INSTALLED.

PORTLAND CEMENT MORTAR FAIRING COURSE		
STATION TO STATION	O/S	QUANTITY
192+26.37 TO 193+98.29	12' LT TO 12' RT	1548 FOOT
TOTAL		1548 FOOT

SAW CUTTING		
STATION	O/S	QUANTITY
190+25	11' RT TO 11' LT	22 FOOT
195+75	11' RT TO 11' LT	22 FOOT
TOTAL		44 FOOT

FURNISHING & ERECTING RIGHT OF WAY MARKERS		
STATION	O/S	QUANTITY
190+25	75' LT	1.0 EACH
190+25	65' RT	1.0 EACH
195+75	75' LT	1.0 EACH
195+75	60' RT	1.0 EACH
TOTAL		4.0 EACH

SHELBY COUNTY
 NEOGA BRIDGE PROJECT
 F.A.S. 656
 SECTION 06-00265-00-BR
 DETAILS