

**RIPRAP SCHEDULE**

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)			DEPTH "X" (FOOT)	STONE RIPRAP CLASS A4 (SQ YD)	STONE RIPRAP CLASS A6 (SQ YD)	FILTER FABRIC (SQ YD)	AGGREGATE BEDDING (TON)
		"A"	"B"	"C"					
HERITAGE BIKEWAY									
STA. 169+00.00 - 19.00' RT TO STA. 169+30.18 - 18.00' RT	30	18	0	0	11	56.7		20	
STA. 175+67.05 - 12.79' RT TO STA. 174+82.05 - 13.00' RT	15	0	15	0	0	25	25	9	
STA. 191+23.29 - 20.51' LT TO STA. 191+43.29 - 21.06' LT	20	0	0	15	10	33.3	33.3	11	
STA. 220+93.81 - 62.47' RT TO STA. 221+2.66 - 61.38' RT	10	3	4	3	2	11.1		4	
STA. 258+17.31 - 15.30' LT TO STA. 258+32.31 - 15.30' LT	15	3	6	2	2	18.3	18.3	6	
STA. 273+40.02 - 16.43' RT TO STA. 273+45.01 - 16.10' RT	5	0	5	0	0	2.8	2.8	1	
STA. 300+13.05 - 18.26' LT TO STA. 300+18.77 - 32.13' LT	15	3	4	3	1	13.3	13.3	5	
STA. 369+26.69 - 20.00' RT TO STA. 369+36.69 - 20.00' RT	10	3	4	3	3	11.1	11.1	4	
STA. 369+39.81 - 25.78' LT TO STA. 369+49.66 - 27.54' LT	10	3	4	3	3	11.1	11.1	4	
STA. 463+75.77 - 78.97' RT TO STA. 463+83.69 - 80.11' RT	8	3	2	3	1	6.5	6.5	2	
STA. 485+19.49 - 29.61' RT TO STA. 485+19.49 - 47.57' RT	18	0	29.5	0	0		58.9	27	
<b>TOTAL</b>						<b>189</b>	<b>59</b>	<b>248</b>	<b>92</b>

NOTE: AGGREGATE BEDDING QUANTITY PROVIDED FOR INFORMATION ONLY  
 \*PLEASE REFER TO RIPRAP DETAIL ON SHEET 256 FOR APPLICATION OF DIMENSIONS.

**SEEDING SCHEDULE**

STATION	SEEDING CLASS 2 (ACRE)	MOWING (ACRE)	NITROGEN FERT NUTR (POUND)	PHOSPHORUS FERT NUTR (POUND)	POTASSIUM FERT NUTR (POUND)	MULCH METHOD 2 (TON)
HERITAGE BIKEWAY						
STA. 103+29.81 TO STA. 525+13.44	14.7	14.7	1323.0	1323.0	1323.0	29.4
<b>TOTAL</b>	<b>14.7</b>	<b>14.7</b>	<b>1323</b>	<b>1323</b>	<b>1323</b>	<b>29.4</b>

**INLET AND PIPE PROTECTION SCHEDULE**

STATION	INLET AND PIPE PROTECTION (EACH)
HERITAGE BIKEWAY	
STA. 163+05.51 - 14.75' RT	1
STA. 191+96.83 - 22.00' RT	1
STA. 273+91.69 - 13.01' RT	1
STA. 273+97.43 - 16.30' LT	1
STA. 281+80.14 - 16.73' RT	1
STA. 312+87.02 - 34.57' RT	1
STA. 335+15.52 - 22.18' LT	1
STA. 352+25.95 - 26.42' LT	1
STA. 368+82.44 - 20.00' RT	1
STA. 368+96.25 - 18.01' LT	1
STA. 369+58.91 - 16.55' LT	1
STA. 436+97.61 - 18.03' LT	1
STA. 463+58.80 - 14.14' RT	1
STA. 491+65.70 - 24.64' LT	1
STA. 495+22.19 - 16.77' LT	1
<b>TOTAL</b>	<b>15</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION	TYPE	PAINT PAVEMENT MARKING		
		LINE 4" YELLOW (FOOT)	LINE 6" WHITE (FOOT)	LINE 12" WHITE (FOOT)
HERITAGE BIKEWAY				
STA. 103+29.81 TO STA. 525+13.44				
	SKIP-DASH 3'-9'	9945		
	CENTERLINE	1849		
	CROSSWALK		309	
	DIAGONALS			312
	STOP LINE			90
<b>TOTAL</b>		<b>11794</b>	<b>309</b>	<b>402</b>

**PAVEMENT MARKING REMOVAL SCHEDULE**

STATION	PAVEMENT MARKING REMOVAL (SQ FT)
HERITAGE BIKEWAY	
STA. 163+79.40 - 2.79' LT TO STA. 164+10.61 - 3.40' LT	31.2
STA. 163+79.42 - 4.22' RT TO STA. 164+10.75 - 3.60' RT	31.3
<b>TOTAL</b>	<b>63</b>