

SIGN SCHEDULE

LOCATION	LT / RT	PROPOSED OFFSET (FT)	DESCRIPTION	SIGN PANEL TYPE 1 (SQ FT)	WOOD SIGN SUPPORT (FOOT)
OLD MADISON ROAD					
STA. 102+75.00	LT	20.05	W14-3 - 48X48X36	6.00	12
STA. 115+25.00	RT	25.00	W14-3 - 48X48X36	6.00	12
TOTAL				12	24

TEMPORARY RAMP SCHEDULE

LOCATION	TEMPORARY RAMP (SQ YD)
OLD MADISON ROAD	
STA. 101+14.67 TO STA. 101+19.67	13
STA. 111+45.51 TO STA. 111+46.85	14
STA. 148+01.26 TO STA. 148+06.26	41
TOTAL	68

SURFACE REMOVAL (BUTT JOINT)

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL BUTT JOINT (SQ YD)
OLD MADISON ROAD		
STA. 101+14.67 TO STA. 101+44.67	78.7	
STA. 111+33.49 RT TO STA. 111+59.24 RT	29.1	
STA. 147+76.26 TO STA. 148+06.26		153.2
TOTAL	108	153