

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	CONSTR. CODE
					ROADWAY 0006 RURAL
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	2282	2282	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	300	300	
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	240	240	
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	2680	2680	
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	60	60	
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	42	42	
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	1223	1223	
44213000	PATCHING REINFORCEMENT	SQ YD	1324	1324	
44213200	SAW CUTS	FOOT	2862	2862	
44213204	TIE BARS 3/4"	EACH	458	458	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	14	14	
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	2210	2210	
60108106	PIPE UNDERDRAINS, TYPE 1, 6"	FOOT	2150	2150	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	650	650	

MODEL: \\MODELNAME FILE: \\... \\\\ILLINOIS.GOV.PWDOT\Documents\DOT\_Office\District 8\Projects\DR-76M07\CADD\DATA\CAD\Sheet\DR-76M07-414-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	CONSTR. CODE
					ROADWAY 0006 RURAL
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2150	2150	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3330	3330	
* 78004100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LETTERS AND SYMBOLS	SQ FT	28	28	
* <del>78004230</del>	<del>PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 6"</del>	<del>FOOT</del>	<del>3330</del>	<del>3330</del>	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	84	84	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	84	84	
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	2800	2800	

\* SPECIALTY ITEM

△ REV 2/22/19

REV. - MS

USER NAME = jeffersons	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = 100.1611' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = 11/27/2018	DATE - _____	REVISED - _____

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET \_\_\_\_\_ OF \_\_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	14-1PP-DR-1	CLINTON	7	3
CONTRACT NO. 76M07				
ILLINOIS FED. AID PROJECT				

MODEL: \\MODEL\NAMES  
FILE NAME: p:\11884EBID\NITEG.illinois.gov\PWIDOT\Documents\DOT Offices\District 8\Projects\1876M07\CADD\Drawings\CAD\Drawings\1876M07-sht-schedule.dgn

HOT-MIX ASPHALT REMOVAL AND REPLACEMENT SCHEDULE							
STA.	DL/PL	LENGTH	WIDTH	HOT-MIX ASPHALT SURFACE REMOVAL 3.5"	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, 2"	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90, 1.5"
		FOOT	FOOT	SQYD	POUNDS	TONS	TONS
I-64 EASTBOUND							
1802+15	DL	100	12	134	91	15	12
1802+15	PL	100	12	134	91	15	12
1803+46	DL	100	12	134	91	15	12
1803+46	PL	100	12	134	91	15	12
1836+93	DL	100	12	134	91	15	12
1836+93	PL	100	12	134	91	15	12
1840+67	DL	100	12	134	91	15	12
1840+67	PL	100	12	134	91	15	12
1852+98	DL	100	12	134	91	15	12
1852+98	PL	100	12	134	91	15	12
I-64 WESTBOUND							
1854+73	DL	100	12	134	91	15	12
1854+73	PL	100	12	134	91	15	12
1842+82	DL	100	12	134	91	15	12
1843+82	PL	100	12	134	91	15	12
1839+60	DL	100	12	134	91	15	12
1839+60	PL	100	12	134	91	15	12
1803+02	DL	100	12	134	91	15	12
1803+02	PL	100	12	134	91	15	12
1801+70	DL	100	12	134	91	15	12
1801+70	PL	100	12	134	91	15	12
TOTAL				2680	2282*	300	240


\* TOTAL QUANTITY FOR TACK COAT EQUAL TO THE SUM OF QUANTITIES FROM THE HOT-MIX ASPHALT R&R SCHEDULE AND THE PATCHING SCHEDULE

PAVEMENT MARKING SCHEDULE			
Station	DL/PL	RAISED REFLECTIVE PAVEMENT MARKER	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"
		EACH	FOOT
I-64 EASTBOUND			
1458+68	DL	8	313
1476+63	DL	2	25
1503+34	DL	2	8
1503+97	DL	2	13
1513+15	DL	2	57
1621+33	DL	2	15
1622+01	DL	2	8
1622+27	DL	2	19
1622+69	DL	2	50
1672+90	DL	2	63
1738+56	DL	2	38
1796+09	DL	2	13
1802+15	DL	4	125
1802+15	PL		100
1803+46	DL	4	125
1803+46	PL		100
1836+93	DL	4	125
1836+93	PL		100
1840+67	DL	4	125
1840+67	PL		100
1852+98	DL	4	125
1852+98	PL		100
I-64 WESTBOUND			
1736+79	DL	6	250
1622+06	DL	2	8
1620+90	PL	4	125
1620+74	DL	2	75
1854+73	DL	4	125
1854+73	PL		100
1842+82	DL	4	125
1842+82	PL		100
1839+60	DL	4	125
1839+60	PL		100
1803+02	DL	4	125
1803+02	PL		100
1801+70	DL	4	125
1801+70	PL		100
TOTAL		84	3330

1

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"

1 REV 2/22/19

USER NAME = jeffersons	DESIGNED - _____	REVISED -  2/22/19
	DRAWN - _____	REVISED - _____
PLOT SCALE = 99.9524' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = 11/26/2018	DATE - _____	REVISED - _____

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET 1 OF 1 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	14-1PP-DR-1	CLINTON	7	5
CONTRACT NO. 76M07				
ILLINOIS FED. AID PROJECT				